1/4/2005

SUBJECT: FAI Route 90/94

Project IM-094-3(372)058 Section 2004-097DTR

Cook County

Item No. 83, 01-21-2005 Letting

Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised page i if the Table of Contents.
- 2. Revised page 23 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine Engineer of Design and Environment

By: Ted B. Walschleger, P. E.

Tett Deluklyon A.E.

Engineer of Project Management

cc: Diane O'Keefe; Roger Driskell; Jim White; Design & Environment File

TK/cah

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
COORDINATION WITH ADJACENT AND/OR OVERLAPPING CONTRACTS	1
CONTRACTOR COOPERATION	2
ADVANCED PUBLIC NOTIFICATION	2
TEMPORARY INFORMATION SIGNING	2
CHANGEABLE MESSAGE SIGNS	3
CONSTRUCTION AIR QUALITY - DUST CONTROL	4
CONSTRUCTION AIR QUALITY-DIESEL VEHICLE EMISSIONS CONTROLS	7
CONSTRUCTION NOISE MITIGATION	9
ENVIRONMENTAL DEFICIENCY DEDUCTION	10
CONTRACTOR OFF-STREET PARKING RESTRICTION	11
KEEPING THE EXPRESSWAY OPEN TO TRAFFIC	11
FAILURE TO OPEN TRAFFIC LANES TO TRAFFIC	12
TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	12
TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	
AUTHORITY OF RAILROAD ENGINEER (BDE)	
EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE)	16
FLAGGER VESTS (BDE)	16
MINIMUM LANE WIDTH WITH LANE CLOSURE (BDE)	
PARTIAL PAYMENTS (BDE)	
PAYMENTS TO SUBCONTRACTORS (BDE)	18
PERSONAL PROTECTIVE EQUIPMENT (BDE)	19
PORTABLE CHANGEABLE MESSAGE SIGNS (BDE)	19
TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE)	20
WORK ZONE PUBLIC INFORMATION SIGNS (BDE)	21
WORK ZONE SPEED LIMIT SIGNS (BDE)	21
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	22
COMPLETION DATE PLUS GUARANTEED WORKING DAYS	23
STORM WATER POLLUTION PREVENTION PLAN	24
CONTRACTOR CERTIFICATION STATEMENT	37
RAILROAD PROTECTIVE LIABILITY INSURANCE	39
CONTRACTOR'S DAILY WORK SCHEDULE	40
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	41

Delete the fourth paragraph of Article 702.05(a) of the Standard Specifications.

Revise the sixth paragraph of Article 702.05(a) of the Standard Specifications to read:

"When the work operations exceed four days, all signs shall be post mounted unless the signs are located on the pavement or define a moving or intermittent operation. When approved by the Engineer, a temporary sign stand may be used to support a sign at 1.2 m (5 ft) minimum where posts are impractical. Longitudinal dimensions shown on the plans for the placement of signs may be increased up to 30 m (100 ft) to avoid obstacles, hazards or to improve sight distance, when approved by the Engineer. "ROAD CONSTRUCTION AHEAD" signs will also be required on side roads located within the limits of the mainline "ROAD CONSTRUCTION AHEAD" signs."

Delete all references to "Type 1A barricades" and "wing barricades" throughout Section 702 of the Standard Specifications.

COMPLETION DATE PLUS GUARANTEED WORKING DAYS

The Contractor shall complete all contract items and safely open all roadways to traffic by 11:59 PM on, May 13, 2005 except as specified herein.

The Contractor will be allowed to complete all clean-up work and punch list items within $\underline{5}$ guaranteed working days after the completion date for opening the roadway to traffic. Under extenuating circumstances the Engineer may direct that certain items of work, not affecting the safe opening of the roadway to traffic, may be completed within the guaranteed working days allowed for clean up work and punch list items. Temporary lane closures for this work may be allowed at the discretion of the Engineer.

Article 108.09 of the Standard Specifications or the Special Provision for Failure to Complete the Work on Time, if included in this contract, shall apply to both the completion date and the number of working days.