F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-097DTR	COOK	21	5
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

62838

SUMMARY OF QUANTITIES

Y004

CODE NO.	ITEM	UNIT	QUANTITY	URBAN 90% FED. 10% STATE ROADWAY Y003
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	360	360
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	254	254
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	39	39
67100100	MOBILIZATION	L SUM	1	1
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
XX005238	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	CU YD	28	28
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

TREE REMOVAL SCHEDULE

STATION	OFFSET	TREE REMOVAL (6-15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)
WELLS STREET		UNIT	UNIT
517+16	6' RT	10	
519+21	17' RT		18
519+99	21' RT	13	
520+16	19' RT	6	
520+26	37' RT	6	
520+73	24' RT	7	
520+82	21' RT	6	
521+00	24' RT	6	
521+05	25' RT	6	
521+27	38' RT	8	
521+45	7' RT	6	
521+53	8' RT	6	
522+45	6' RT	8	
522+52	19' RT		30
522+65	15' RT	11	
522+74	15' RT	7	
522+90	6' RT	15	
523+07	7' RT	6	
523+13	7' RT	6	
523+21	6' RT	13	
523+37	7' RT		20
523+40	24' RT	12	
523+54	11' RT		17
523+78	9' RT	8	
523+84	14' RT		18
524+22	21' RT		18
524+28	8' RT	14	
524+99	6' RT		18
525+83	13' RT		26
525+99	8' RT	6	
526+17	13' RT		18
531+18	25' RT	6	
532+67	22' RT	12	
532+85	26' RT	12	
533+06	21' RT	9	
533+17	22' RT	6	
533+67	26' RT	13	
	SUB-TOTAL	244	183

TREE REMOVAL SCHEDULE

STATION	OFFSET	TREE REMOVAL (6-15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)
WENTWORTH AVENUE		UNIT	UNIT
105+40	44' LT		16
107+24	47' LT	14	
112+97	22' LT		22
113+08	19' LT		16
113+84	21' LT	9	
114+59	23' LT	10	
118+56	8' LT	10	
119+58	11' LT	6	
119+69	9' LT	10	
119+70	9' LT	6	
119+77	9' LT	12	
119+88	8' LT	6	
120+14	9' LT	6	
120+20	9' LT	9	
120+33	8' LT	6	
123+72	8' LT	6	
123+73	8' LT	6	
130+10	24' LT		17
	SUB-TOTAL	116	71

TREE REMOVAL SCHEDULE SUMMARY

LOCATION	TREE REMOVAL (6-15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)
	UNIT	UNIT
WENTWORTH AVENUE	116	71
WELLS STREET	244	183
TOTALS	360	254

CTE ENGINEERS
CONSOER TOWNSEND ENVIRODYNE ENGINEERS, INC.
303 EAST WACKER DRIVE, SUITE 600
CHICAGO ILLINOIS 60601-5202, PHONE: (312) 938-0300

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63rd ST TO 59th ST (TREE REMOVAL)

SUMMARY OF QUANTITIES
SCHEDULE OF QUANTITIES

SCALE: NONE
DRAWN BY: NJH
DATE: October 22, 2004
CHECKED BY: RMG

MLP40468\CIVIL\NE CHI\SCADL_CHI\90C09SHT\S0090C0012A.SHT
10/12/2004 9:45:23 AM