

SEWER TELEVISION SCHEDULE - WENTWORTH AVENUE

STR. NO.	FROM		TO			PIPE DIA. (IN)	LENGTH (FOOT)	TELEWISE BEFORE CONTRACT 62693	TELEWISE AFTER CONTRACT 62693
	STATION	OFFSET	STR. NO.	STATION	OFFSET				
01	100+15	2.90' LT	02	100+69	3.44' LT	30	54	X	X
02	100+69	3.44' LT	03	101+94	3.45' LT	30	125	X	X
03	101+94	3.45' LT	04	102+63	3.17' LT	30	69	X	X
04	102+63	3.17' LT	05	103+58	3.16' LT	30	95	X	X
05	103+58	3.16' LT	06	104+18	3.75' LT	30	60	X	X
06	104+18	3.75' LT	07	104+68	6.71' RT	30	50	X	X
07	104+68	6.71' RT	08	105+68	6.98' RT	36	100	X	X
08	105+68	6.98' RT	09	106+47	5.82' RT	36	79	X	X
09	106+47	5.82' RT	10	108+48	5.02' RT	24	203	X	X
09	106+47	5.82' RT	10	108+48	5.02' RT	24	203	X	X
10	108+48	5.02' RT	11	110+68	5.18' RT	36	220	X	X
11	110+68	5.18' RT	12	110+76	15.23' RT	30	13	X	X
12	110+76	15.23' RT	13	110+90	4.13' RT	18	18	X	X
13	110+90	4.13' RT	14	111+23	4.11' RT	18	33	X	X
14	111+23	4.11' RT	EC09	112+88	5.63' RT	18	165	X	X
EC09	112+88	5.63' RT	ED15	116+03	6.67' RT	18	316		X
ED15	116+03	6.67' RT	15	115+98	31.60' RT	24	26	X	X
ED15	116+03	6.67' RT	EE17	119+35	7.50' RT	24	332		X
EE17	119+35	7.50' RT	EE18	121+15	6.50' RT	24	180		X
EE18	121+15	6.50' RT	EE19	122+75	11.50' RT	24	160		X
EE19	122+75	11.50' RT	EF11	124+45	10.00' RT	24	170		X
EF11	124+45	10.00' RT	16	124+43	20.37' RT	42	11	X	X
EF11	124+45	10.00' RT	EF10	126+58	9.00' RT	24	213		X
EF10	126+58	9.00' RT	EG04	128+84	9.00' RT	24	230		X
EG04	128+84	9.00' RT	17	131+12	8.83' RT	24	228		X
17	131+12	8.83' RT	18	131+11	25.46' RT	18	17	X	X
18	131+11	25.46' RT	19	131+10	131.91' RT	18	107	X	X
							SUB-TOTALS	1,648	3,477

SEWER TELEVISION SCHEDULE - WELLS STREET


STR. NO.	FROM		TO			PIPE DIA. (IN)	LENGTH (FOOT)	TELEWISE BEFORE CONTRACT 62693	TELEWISE AFTER CONTRACT 62693
	STATION	OFFSET	STR. NO.	STATION	OFFSET				
50	22+04	3.12' RT	51	508+02	7.60' LT	30	137	X	X
51	508+02	7.60' LT	52	508+02	121.35' LT	18	114	X	X
51	508+02	7.60' LT	53	509+53	14.77' LT	15	151	X	X
53	509+53	14.77' LT	54	511+05	12.70' LT	15	152	X	X
55	513+84	15.21' LT	56	514+79	13.90' LT	8	95	X	X
56	514+79	13.90' LT	57	514+99	77.84' RT	12	94	X	X
58	515+76	18.06' LT	59	517+51	16.03' LT	15	175	X	X
59	517+51	16.03' LT	60	519+40	14.51' LT	15	189	X	X
60	519+40	14.51' LT	61	521+22	13.28' LT	15	182	X	X
61	521+22	13.28' LT	62	522+88	13.90' LT	30	166	X	X
62	522+88	13.90' LT	63	524+50	14.09' LT	30	162	X	X
63	524+50	14.09' LT	64	524+50	55.03' LT	15	41	X	X
63	524+50	14.09' LT	65	526+12	14.21' LT	30	162	X	X
65	526+12	14.21' LT	66	527+85	15.31' LT	30	173	X	X
66	527+85	15.31' LT	67	529+47	14.30' LT	30	162	X	X
67	529+47	14.30' LT	68	531+17	16.64' LT	30	170	X	X
68	531+17	16.64' LT	69	532+80	14.09' LT	30	163	X	X
69	532+80	14.09' LT	70	534+51	15.43' LT	30	171	X	X
							SUB-TOTALS	2,659	2,659

SEWER TELEVISION SCHEDULE - SUMMARY

LOCATION	TELEWISE BEFORE CONTRACT 62693	TELEWISE AFTER CONTRACT 62693	TOTALS
WENTWORTH AVE	1,648	3,477	5,125
WELLS ST	2,659	2,659	5,318
TOTALS	4,307	6,136	10,443

NOTES:

- THE EXISTING COMBINED SEWERS BETWEEN STATIONS 112+88 AND 131+12 ALONG WENTWORTH AVENUE SHOULD NOT BE TELEVISED SINCE THEY WILL BE REMOVED AND REPLACED IN CONTRACT NO. 62693. THESE PROPOSED SEWERS WILL BE TELEVISED AFTER THE COMPLETION OF CONTRACT NO. 62693.
- SUB-TOTALS ARE THE SUMMATION OF PIPE LENGTH BEING TELEVISED EITHER PRIOR TO OR AFTER THE COMPLETION OF CONTRACT NO. 62693.



REVISIONS	NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63rd ST TO 59th ST (SEWER TELEVISION)

SCHEDULE OF QUANTITIES

SCALE: NONE
DATE: October 22, 2004
DRAWN BY: NJH
CHECKED BY: RMG

10/14/2004 10:33:55 AM