

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL	URBAN - 90% FED, 10% STATE		100% CITY Y060	
				DAN RYAN J000-2A	UTILITY Y060	STA. 2232+61 TO 2240+21	STA. 2250+80 TO 2259+05
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	652		652		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	364		364		
20101000	TEMPORARY FENCE	FOOT	849	849			
20101700	SUPPLEMENTAL WATERING	UNIT	18.8		11.9	6.3	0.6
20200100	EARTH EXCAVATION	CU YD	310		293	16	1
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	70		65	4	1
20700220	POROUS GRANULAR EMBANKMENT	CU YD	673	673			
20800150	TRENCH BACKFILL	CU YD	4705		4705		
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5290	3379	1765	140	6
* 21101630	TOPSOIL FURNISH AND PLACE, 8"	SQ YD	5180		5180		
21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	168		126	24	18
* 25000210	SEEDING, CLASS 2A	ACRE	2.14	0.7	1.41	0.01	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	195	63	129	3	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	195	63	129	3	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	195	63	129	3	
* 25100630	EROSION CONTROL BLANKET	SQ YD	10263	3379	6813	71	
* 25200110	SODDING, SALT TOLERANT	SQ YD	207		132	69	6
28000400	PERIMETER EROSION BARRIER	FOOT	2587	643	1944		
28000510	INLET FILTERS	EACH	47	4	33	3	7
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	10,450		8547	1013	890
35300510	PORTLAND CEMENT CONCRETE BASE COURSE 10 1/2"	SQ YD	9,727		7,952	908	867
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	131		131		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8.3	0.2	5.6	1.5	1.0
40600300	AGGREGATE (PRIME COAT)	TON	41	1	28	7	5
40600895	CONSTRUCTING TEST STRIP	EACH	1		1		
40600990	TEMPORARY RAMP	SQ YD	16		13	1	2
42000540	PORTLAND CEMENT CONCRETE PAVEMENT 12"	SQ YD	25		25		
42001300	PROTECTIVE COAT	SQ YD	855	230	596	28	1
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 8"	SQ YD	5		5		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	458		458		
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	9,824		5,826	2,528	1,470
44000100	PAVEMENT REMOVAL	SQ YD	10,284	256	8,148	991	889
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	5		5		

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL	URBAN - 90% FED, 10% STATE		100% CITY Y060	
				DAN RYAN J000-2A	UTILITY Y060	STA. 2232+61 TO 2240+21	STA. 2250+80 TO 2259+05
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2583.5	40	2411.5	126.0	6.0
44000600	SIDEWALK REMOVAL	SQ FT	458		458		
44001980	CONCRETE BARRIER REMOVAL	FOOT	224	224			
44004250	PAVED SHOULDER REMOVAL	SQ YD	632	9	623		
44004510	PORTLAND CEMENT CONCRETE SHOULDER REMOVAL	SQ YD	161	161			
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	666	9	657		
48300400	PORTLAND CEMENT CONCRETE SHOULDER, 9"	SQ YD	161	161			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1		
50300225	CONCRETE STRUCTURES	CU YD	8.4	8.4			
50800105	REINFORCEMENT BARS	POUND	1670	1670			
550A1350	STORM SEWERS, CLASS A, TYPE 5, 48"	FOOT	6	6			
550A1640	STORM SEWERS, CLASS A, TYPE 6, 42"	FOOT	4	4			
552A1000	STORM SEWERS JACKED IN PLACE, CLASS A 27"	FOOT	152	152			
552A1300	STORM SEWERS JACKED IN PLACE, CLASS A 36"	FOOT	383	383			
56100700	WATER MAIN, 8"	FOOT	147		137	10	
56101120	WATER MAIN, 24"	FOOT	6120		4528	767	825
56105790	BUTTERFLY VALVES, 24"	EACH	4		4		
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	5		4	1	
56400600	FIRE HYDRANTS	EACH	6		5	1	
60107700	PIPE UNDERDRAIN, 6"	FOOT	160	160			
60202505	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	13		13		
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	4		4		
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
60226600	MANHOLES, DROP TYPE, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
60226730	MANHOLES, DROP TYPE, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1		1		
60247800	JUNCTION CHAMBER	EACH	2	2			
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1			
60300105	FRAME AND GRATE TO BE ADJUSTED	EACH	10		10		
60500040	REMOVING MANHOLES	EACH	9		9		
60500050	REMOVING CATCH BASINS	EACH	32		32		
60500060	REMOVING INLETS	EACH	3		3		
60603800	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12	FOOT	125.5		125.5		

* - SPECIALTY ITEM
 □ - IDOT PAY CODE SFTY-3N
 △ - IDOT PAY CODE Y080

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
 SHEET 1 OF 3

SCALE: NONE DRAWN BY: MPG
 DATE: OCTOBER 4, 2004 CHECKED BY: JJS

Rev.

P:\023733\Road\CIT\scit\scit\03ad09 04/17/2004 04:17:35 PM