F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	1516.1-I-1	COOK	195	7
STA. 2016+35		TO STA. 2353+03		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62872

SUMMARY OF QUANTITIES

	CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL	URBAN - 90% FED, 10% STATE		100% CITY Y060	
					DAN RYAN J000-2A	UTILITY Y060	STA. 2232+61 TO 2240+21	STA. 2250+80 TO 2259+05
	X0324334	ABANDONMENT OF EXISTING WATER MAIN, 8"	EACH	6		5	1	
	X0324335	ABANDONMENT OF EXISTING WATER MAIN, 12"	EACH	1			1	
	X0324342	THRUST RESTRAINT, TYPE A	EACH	2		2		
	X0324343	THRUST RESTRAINT, TYPE B	EACH	2		2		
	X0324352	ABANDONMENT OF EXISTING WATER MAIN, 24"	EACH	2		2		
	X0324735	COMBINED SEWER, DUCTILE IRON PIPE, CLASS 52, TYPE 2, 24"	FOOT	120		120		
	X0324736	COMBINED SEWER, DUCTILE IRON PIPE, CLASS 52, TYPE 2, 30"	FOOT	394		394		
	X0324737	COMBINED SEWER, DUCTILE IRON PIPE, CLASS 52, TYPE 2, 36"	FOOT	667		667		
	X0712400	TEMPORARY PAVEMENT	SQ YD	227	112	115		
	XX005991	RECONNECT WATER SERVICE	EACH	1				1
	X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	1687	12	1180	296	199
	X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	14	14			
	X6022120	MANHOLES, DROP TYPE, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3			
	X6022400	MANHOLES, TYPE A, 3' DIAMETER (INCLUDING FRAMES AND LIDS)	EACH	10		10		
	X6022450	MANHOLES, TYPE B, 3' DIAMETER (INCLUDING FRAMES AND LIDS)	EACH	1		1		
	X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1			
	X7013820	TRAFFIC CONTROL SURVEILLANCE (EXPRESSWAYS)	CAL DA	93	93			
	X7015000	CHANGEABLE MESSAGE SIGNS	CAL MO	20	13	7		
	X7040600	FURNISH TEMPORARY CONCRETE BARRIER	FOOT	1010	460	550		
	XX001490	GATE VALVES, 8"	EACH	10		8	2	
	XX003032	GATE VALVES, 12"	EACH	1			1	
	XX004812	VIDEO TAPING OF SEWERS	FOOT	7014		7014		
	XX005489	STEEL CASINGS, 48"	FOOT	383	383			
	XX011700	WATER MAIN FITTINGS	POUND	5000		5000		
	XX104800	COMBINATION CONCRETE CURB & GUTTER, TYPE B-V.12	FOOT	2418		2286	126	6
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1.0	0.2	0.6	0.1	0.1
⊙	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	18		18		
□	Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1		1		
□	Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	3	1		
□	Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1		1		
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			
	Z0068400	STEEL CASINGS, 42"	FOOT	152	152			
△	Z0076600	TRAINEES	HOUR	1000		1000		

⊙ - NON-PARTICIPATING
✱ - SPECIALTY ITEM
□ - IDOT PAY CODE SFTY-3N
△ - IDOT PAY CODE Y080

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FED, 10% STATE		100% CITY Y060	
				DAN RYAN J000-2A	UTILITY Y060	STA. 2232+61 TO 2240+21	STA. 2250+80 TO 2259+05

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
SHEET 3 OF 3

SCALE: NONE | DRAWN BY: MPG
DATE: OCTOBER 4, 2004 | CHECKED BY: JJS

p:\0237.3\Road\Cltd\sqlt\Dsh033a.dgn 11/19/2004 04:18:22 PM

...\Road\Cltd\sqlt\Dsh033a.dgn 11/19/2004 04:18:22 PM