

PCC / BITUMINOUS SCHEDULE

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	37R-2	OGL	389	16
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT #64157

STATION TO STATION	LENGTH (M)	REMARKS	SURFACE AREA (SQ M)	BIT. PRIME (MT)	AGG. PRIME (MT)	M4830240 PCC SHOULDERS 240 MM (SQ M)	M4202245 PCCP 240 MM (JOINTED) (SQ M)	M3110300 SUB-BASE GRAN MAT TYPE A 300mm (SQ M)	MX406024 BIT. CONC. SURF. CSE. SUPRVE. IX D N70 (50MM) (MTON)	MX408040 INCIDENTAL BIT SURF SUPER (76.2MM) (MTON)	MX408040 INCIDENTAL BIT SURF SUPER (63.5MM) (MTON)	M4400025 BITUMINOUS SURFACE REMOVAL (25.4 MM) (SQ M)	M4400000 BITUMINOUS SURFACE REMOVAL (SQ M)	MZ028415 GEOTECHNICAL REINFORCEMENT (SQ M)	M4402000 PAVEMENT REMOVAL (SQ M)
09/02/04 BITSCHLD															
COLFAX ST.															
10+931.50 TO 10+934.50	3.0	UTT JOIN	17.00	0.05	0.0					1.0		17.0			
10+934.50 TO 10+978.60	44.1		351.80	0.96	0.5			433.6		64.1				433.6	248.6
10+978.60 TO 10+993.90	15.3		319.30			319.3	347.7							347.7	192.3
10+993.90 TO 10+999.00	5.1	TAPER		0.02	0.1				6.8						
11+005.90 TO 11+012.00	6.1	TAPER		0.02	0.1				8.2						
11+007.90 TO 11+025.30	17.4		398.40			398.4	430.7							430.7	237.4
11+025.30 TO 11+043.70	18.4		179.40	0.49	0.3		213.5			32.7				213.5	154.3
1+143.70 TO 1+147.00	3.3	UTT JOIN	25.70	0.07	0.0					1.6		25.7			
WEST ST.															
11+938.40 TO 11+941.10	2.7	UTT JOIN	21.00	0.06	0.0					1.3		21.0			
11+941.40 TO 11+980.30	38.9		263.40	0.72	0.4			335.6		48.0				335.6	269.0
11+980.30 TO 11+993.90	13.6		213.90			213.9	239.1							239.1	196.8
LAFAYETTE ST.															
12+940.80 TO 12+943.90	3.1	UTT JOIN	29.30	0.08	0.0					1.8		29.3			
12+943.90 TO 12+979.70	35.8		345.50	0.95	0.5			411.9		63.0				411.9	358.5
12+979.70 TO 12+993.90	14.2		262.60			262.6	288.9							288.9	202.9
12+993.00 TO 12+999.10	6.1	TAPER		0.02	0.1				8.5						
13+005.60 TO 13+020.00	14.4		263.10			263.1	289.8							289.8	208.1
13+005.90 TO 13+012.00	6.1	TAPER		0.03	0.1				10.4						
13+020.00 TO 13+032.80	12.8		129.80	0.36	0.2		153.5			23.7				153.5	143.0
13+032.80 TO 13+035.90	3.1	UTT JOIN	34.40	0.09	0.1					2.1		34.4			
FRANKLIN ST.															
13+947.00 TO 13+950.00	3.0	UTT JOIN	30.30	0.08	0.0					1.8		30.3			
13+950.00 TO 13+980.50	30.5		279.00	0.76	0.4			335.6		50.9				335.6	306.7
13+980.50 TO 13+993.70	13.2		249.20			249.2	273.7							273.7	191.5
14+005.90 TO 14+012.00	6.1	TAPER		0.02	0.1				8.0						
14+006.10 TO 14+019.80	13.7		253.60			253.6	279.0							279.0	196.5
14+019.80 TO 14+032.90	13.1		124.20	0.34	0.2		148.5			22.6				148.5	128.2
14+032.90 TO 14+035.90	3.0	UTT JOIN	30.00	0.08	0.0					1.8		30.0			
UNNAMED ALLEY															
15+006.50 TO 15+024.00	17.5														69.6
WASHINGTON ST.															
15+941.80 TO 15+944.90	3.1	UTT JOIN	31.80	0.09	0.0					1.9		31.8			
15+944.90 TO 15+979.70	34.8		342.50	0.94	0.5			407.0		62.4				407.0	361.4
15+979.70 TO 15+993.90	14.2		261.60				261.6	287.9						287.9	199.3
16+006.10 TO 16+019.90	13.8		268.00				268.0	293.6						293.6	185.1
16+005.90 TO 16+012.00	6.1	TAPER		0.02	0.1				8.0						
16+019.90 TO 16+043.40	23.5		361.50	0.99	0.5			405.1		65.9				405.1	244.1
16+043.40 TO 16+124.70	81.3	100% city	1384.20	3.79	2.1		1384.2				210.2		482.6	1384.2	
WALNUT ST.															
16+951.80 TO 16+954.90	3.1	UTT JOIN	35.00	0.10	0.1					2.1		35.0			
16+954.90 TO 16+979.70	24.8		250.90	0.69	0.4			296.9		45.7				296.9	274.8
16+979.70 TO 16+992.60	12.9		216.50			216.5	240.4							240.4	203.5
17+005.90 TO 17+012.00	6.1	TAPER		0.04	0.2				16.1						
17+006.10 TO 17+026.10	20.0		558.20				558.2	595.3						595.3	408.3
17+026.10 TO 17+050.00	23.9		363.20	1.00	0.5			407.5		66.2				407.5	350.1
17+050.00 TO 17+123.10	73.1	100% city	1079.40	2.96	1.6						164.0		500.6		
TOTALS				28.09	34.72	1497.80	29289.05	42310.59	1767.64	1048.65	374.20	495.80	983.20	42310.59	24469.70