

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	37R-2	OGLE	389	19
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT #64157				

# DRAINAGE SCHEDULE

STATION	OFFSET	REMARKS	STORM SEWER CLASS A, TYPE 1				STORM SEWER (WATER MAIN REQUIREMENTS) TYPE 1						STORM SEWER CLASS A, TYPE 2		PIPE CULVERTS						END SECTIONS					
			300 MM	375 MM	450 MM	525 MM	300 MM	375 MM	450 MM	525 MM	600 MM	675 MM	375 MM	525 MM	CLASS A TYPE 1 300MM	CLASS A TYPE 2 450MM	CLASS D TYPE 1 450MM	CLASS A TYPE 1 600 MM	TYPE 1 REINFORCED CONC ARCH EQRS 1200 MM	CLASS D TYPE 1 1050MM (ARCH)	PRECAST CONCRETE FLARED END SECTION 300MM	PRECAST CONC. FLARED END SECT-ARCH EQRS 1200MM	END SECTION 450MM	COR STEEL MULTI PIPE END SECT-ARCH, EQRS 1050MM		
METERS			METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	EACH	EACH	EACH	EACH			
FOX RUN LANE																										
4+032.8	4.68 RT	TRANSVERSE	10.63																							
4+032.8	4.64 LT	OUTLET													10.35						1					
BARRY AVENUE																										
4+979.0	4.39 RT	TRANSVERSE	13.08																							
4+985.0	6.59 LT	TIE IN	5.71																							
PERENE AVENUE																										
4+979.4	4.99 RT	TRANSVERSE	12.43																							
4+983.9	6.61 LT	TIE IN	4.55							3.05																
SOUTH MAPLE AVENUE																										
6+950.0	9.18 RT	MANHOLE	35.57																							
6+985.5	6.54 LT	TRANSVERSE	15.24																							
6+987.4	8.81 RT	TIE IN	9.16																							
NORTH MAPLE AVENUE																										
7+016.2	6.48 LT	TRANSVERSE	12.3																							
7+019.0	5.45 RT	TIE IN	9.54																							
33+402.8	10.30 LT	TIE IN	12.32																							
SUMNER STREET																										
7+984.5	6.74 LT	TRANSVERSE	12.62																							
7+985.0	5.86 RT	TIE IN	17.3																							
GRANT STREET																										
9+039.9	9.18 LT	MANHOLE	9.65																							
9+028.9	3.67 RT	TRANSVERSE	9.25																							
9+028.9	5.58 LT	TIE IN	30.48							4.9																
LINCOLN STREET																										
33+714.2	9.64 LT	TRANSVERSE	21.63																							
33+736.0	9.65 LT	TIE IN	11.6																							
9+984.4	8.04 LT	TRANSVERSE	13.22																							
9+984.4	5.18 RT	TIE IN	6.66																							
COLFAX STREET																										
10+983.6	5.77 RT	TRANSVERSE	14.11																							
10+982.5	8.29 LT	TIE IN	8.93																							
11+023.1	8.67 RT	TRANSVERSE	18.64																							
11+015.3	8.93 LT	TIE IN	15.92							6.1																
BANK PARKING LOT																										
33+871.2	13.83 RT	TIE IN	10.58																							
WEST STREET																										
11+987.3	5.65 RT	TIE IN	4.11																							
BURGER KING PARKING LOT																										
33+988.2	17.92 RT	TIE IN	9.19																							
LAFAYETTE STREET																										
12+987.3	7.57 RT	TRANSVERSE	16.78																							
12+987.3	9.22 LT	TIE IN	12.59																							
13+031.1	4.79 RT	TRANSVERSE	9.92																							
13+031.1	5.13 LT	TIE IN	21.66																							
SNYDERS PARKING LOT																										
34+059.8	11.84 LT	TIE IN	3.05							2.13																
34+134.1	11.84 LT	TIE IN	7.92							3.05																
FRANKLIN STREET																										
14+031.2	4.60 RT	TRANSVERSE	9.34																							
14+031.2	4.73 LT	TIE IN	22.61																							
34+144.8	7.09 RT	MANHOLE								24.23																
13+984.7	7.39 LT	TRANSVERSE	13.62																							
13+984.7	6.23 RT	TIE IN	15.62																							
WASHINGTON STREET																										
15+980.0	7.38 LT	TRANSVERSE	14.47																							
15+986.5	6.72 RT	TIE IN	7.63																							
16+015.0	6.68 LT	TRANSVERSE	15.66																							
16+013.0	8.87 RT	TIE IN	10.68							6.1																
WALNUT STREET																										
16+980.0	4.64 RT	TRANSVERSE	11.42																							
16+980.0	6.17 LT	TIE IN	14.01																							
34+384.7	9.76 LT	MAINLINE	10.81																							
17+020.0	9.86 RT	TRANSVERSE																						19.91		
17+018.8	9.84 LT	TIE IN																						16.44		
17+021.5	9.86 RT	TIE IN																						11.83		
TOTAL			961	306.5	220.7	69.2	331.06	74.16	102.9	141.3	83.78	27.33	62.42	10.11	15.35	24.78	9.28	40	48.77	47.54	2	1	2	2		

DATE-TIME  
 DGN-SPEC  
 REF  
 REF  
 REF