F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	37R-2	OGLE	389	63
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT #64157

FINAL SURVEY	BY	DATE
NOTE BOOK	SURVEYED	
NO.	PLOTTED	
	TEMPLATE	
	AREAS	
	AREAS CHECKED	

ORIGINAL SURVEY	BY	DATE
NOTE BOOK	SURVEYED	
	PLOTTED	
	TEMPLATE	
	AREAS	
NO.	AREAS CHECKED	

BRADLEY & CHARLENE HAYE

MICHAEL A. KOLECKE

MARY J. HOPP

DEBRA L. POWLESS

JAMES CARR

JAMES R. & MARY JANE MCNAMES

CAROL E. CAPES

SAVE TREES

EXISTING R.O.W.

PR R.O.W.

TEMP EASE

CONST LIMITS

IMPROVEMENT ENDS STA. 5+940

3.048m BITUMINOUS BUTT JOINT

PERENE AVE

9.9 m

5+950

84.2273°

STA. 33+215.841 IL RTE 2= STA. 6+000 PERENE AVE.

1,331.200

6 m

6.1 m

5.7 m

7.2 m

6.8 m

PE

R

X = TREE REMOVAL

0 10 20

Scale In Meters

ex = 0.093
K = 5
20.000 m V.C.

ex = 0.045
K = 11
20.000 m V.C.

220.682

-0.910%

-2.725%

-2.725%

+1.000%

+0.13%

+1.995%

VPI STA. 5+959.999
ELEVATION 220.500

+949.999 EL. 220.591

+969.999 EL. 220.227

VPI STA. 5+979.999
ELEVATION 219.955

+989.999 EL. 220.055

VPI STA. 5+993.713
ELEVATION 220.06

VPI STA. 6+000.00
ELEVATION 220.185

VPI STA. 6+001.984
ELEVATION 220.225

222.5

220

217.5

215

EARTH EX=212 CU M
EMBANKMENT=0 CU M
WASTE=159 CU M

220.649
220.591

220.368
220.115

5+937.5 5+950.0 5+962.5 5+975.0 5+987.5 6+000.0

PERENE AVENUE

Thu Sep 02 11:26:45 2004
c:\projects\m208096\plan2.dgn