

F.A. RTE. 412	SECTION (50-4B-1)I	COUNTY LASALLE	TOTAL SHEETS 20	SHEET NO. 3
------------------	-----------------------	-------------------	--------------------	----------------

# SUMMARY OF QUANTITIES

CONSTRUCTION CODE: **1000**

CODE NO.	ITEM	UNIT	100% STATE TOTAL QUANTITY
31200100	STABILIZED SUB-BASE 4"	SQ YD	1110
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	332
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1094
44000700	APPROACH SLAB REMOVAL	SQ YD	1068
<b>44001430</b>	BITUMINOUS SHOULDER REMOVAL	<b>SQ YD</b>	447
44001980	CONCRETE BARRIER REMOVAL	FOOT	260
44002100	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT REMOVAL	SQ YD	358
44004510	PORTLAND CEMENT CONCRETE SHOULDER REMOVAL	SQ YD	426
48101200	AGGREGATE SHOULDER TY B	TON	10
48300500	PORTLAND CEMENT CONCRETE SHOULDER 10"	SQ YD	964
63700300	CONCRETE BARRIER, DOUBLE FACE (MODIFIED)	FOOT	240
63700805	CONCRETE BARRIER TRANSITION	FOOT	20
67100100	MOBILIZATION	L SUM	1
70100305	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	L SUM	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1
70100805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	70
70300220	TEMPORARY PAVEMENT MARKING, LINE 4"	FOOT	3284
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1083
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	3284
78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	150
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1083
XX004896	AGGREGATE FOR UNDERDRAINS	CU YD	28
* X0323984	PORTABLE TEMPORARY BARRIER SYSTEM	FOOT	1122
* X0323985	RELOCATE PORTABLE TEMPORARY BARRIER SYSTEM	FOOT	1082
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1

\* SFTY 3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT.  
HORIZ.  
DATE 08/16/04

DRAWN BY RLW  
CHECKED BY

cmaln05/cm301/details.dgn