CONTRACT NO. 66528

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
649	*	LIVINGSTON	15	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*(16)RS-4,(17,28)RS-2

PAVEMENT MARKING

LOCATION	PAINT 4" WHITE FOOT	PAINT 4" YELLOW FOOT	PAINT 6" YELLOW FOOT	THERMOPLASTIC LTRS & SYM WHITE SQ FT	THERMOPLASTIC 4" WHITE FOOT	THERMOPLASTIC 4" YELLOW FOOT	THERMOPLASTIC 6" YELLOW FOOT	THERMOPLASTIC 8" WHITE FOOT	THERMOPLASTIC 12" YELLOW FOOT	THERMOPLASTIC 12" WHITE FOOT	THERMOPLASTIC 18" WHITE FOOT	THERMOPLASTIC 24" WHITE FOOT	TEMPORARY PAINT LTRS & SYM WHITE SQ FT	TEMPORARY PAINT 4" YELLOW FOOT	TEMPORARY PAINT 6" YELLOW FOOT	TEMPORARY PAINT 8" WHITE FOOT	TEMPORARY PAINT 12" YELLOW FOOT	TEMPORARY PAINT 24" WHITE FOOT	RAISED REFL PAVT MARKERS CRYSTAL EACH	RAISED REFL PAVT MARKERS AMBER EACH	SHORT TERM PVT MK FOOT
STA 101+90 TO STA 249+04																					
EDGELINE	29428																				
SKIP DASH CENTERLINE			3570												7140					184	4414
NO PASSING ZONES - EB																					
101+90 TO 110+50		860												1720							
178+70 TO 186+00		730												1460							
195+00 TO 205+05		1005												2010							
221+00 TO 228+90		790												1580							
244+04 TO 249+04		500												1000							
NO PASSING ZONES - WB																					
111+50 TO 120+48		898												1796							
189+15 TO 195+90		675												1350							
201+65 TO 210+25		860												1720							
230+00 TO 236+50		650												1300							
STA 249+04 TO STA 254+84					1160	2320			150					4640			300			30	696
STA 254+84 TO STA 257+86				62.4	1150	410	80	440		150		70	124.8	820	160	880		140	18	17	696
STA 257+86 TO STA 263+66					1160	2320			150					4640			300			30	696
STA 263+66 TO STA 322+87.50																					
EDGELINE	11843																				
SKIP DASH CENTERLINE			1380												2760					74	1776
NO PASSING ZONES - EB																					
295+70 TO 310+10		1440												2880							
NO PASSING ZONES - WB																					
263+66 TO 268+66		500												1000							
306+00 TO 320+25		1425												2850							
STA 322+87.50 BK = STA 322+85.10 AH																					
STA 322+85.10 TO STA 710+86																					
EDGELINE	77602																				
SKIP DASH CENTERLINE			9700												19400					485	11640
NO PASSING ZONES - EB																					
429+90 TO 437+90		800												1600							
NO PASSING ZONES - WB																					
440+95 TO 449+20		825												1650							
AERIAL SPEED CHECK ZONES											36										
TOTALS	130831		14650	62.4	8520		80	440	450		36	70	124.8	34016	29460	880	600	140	838		19918

NOTE: USE LARGE SIZE ARROWS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 11/3/2004
FILE NAME = $FILEL$
PLOT SCALE = $SCALE$
REFERENCE = REF