

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
71	(116,117)RS-1	*	12	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* MCLEAN, CHAMPAIGN, FORD				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	CONSTRUCTION CODE TYPE:				
			80% FED. 20% STATE TOTAL QUANTITY	MCLEAN CO. STA. 8+55 TO STA. 289+48	I000 CHAMPAIGN CO. STA. 289+48 TO STA. 306+51	FORD CO. STA. 306+51 TO STA. 594+14	SFTY-2A MCLEAN CO. SN 057-2024
20400800	FURNISHED EXCAVATION	CU YD	79	43		36	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	14194	7073	348	6767	6
40600300	AGGREGATE (PRIME COAT)	TON	356	178	9	169	
40600400	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	TON	65	32	2	31	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600990	TEMPORARY RAMP	SQ YD	506	244	29	233	
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	177415	88412	4345	84583	75
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	1539	730	41	768	
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	114	65		49	
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	58			58	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2164	1025	57	1082	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	2		2	
67100100	MOBILIZATION	L SUM	1	0.5		0.5	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.4		0.6	
70100600	TRAFFIC CONTRAL AND PROTECTION, STANDARD 701336	L SUM	1	0.4		0.6	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	17666	8525	511	8630	
70300625	TEMPORARY PAINT PAVEMENT MARKING - LINE 4"	FOOT	8158	8158			
70300635	TEMPORARY PAINT PAVEMENT MARKING - LINE 6"	FOOT	28840	13820	760	14260	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1983	968	57	958	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	92.4	92.4			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	190	190			
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	440	440			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	210	210			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	58	58			
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	125119	59109	3008	63002	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	15210	6930	380	7900	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	767	390	19	358	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	32	12	4	16	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	767	390	19	358	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	14441	7156	365	6914	6
X4066735	LEVELING BINDER (HAND METHOD), SUPERPAVE N50	TON	86	43	2	41	
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	7126	3374	188	3561	3
XX004949	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE	TON	615	361		254	
Z0021700	EXPANSION JOINT REHABILITATION	FOOT	156	52		104	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY