

SUMMARY OF QUANTITIES

PAP. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
618	33(EXT) BR	MCDONOUGH	63	5
STA.	TO STA.			
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		

CONT. *68266

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		X028-2A	
20200100	EARTH EXCAVATION	CU YD	5003	5003	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	88	88	
20400800	FURNISHED EXCAVATION	CU YD	2621	2621	
21101615	TOP SOIL FURNISH AND PLACE, 4"	SO YD	10017	10017	
25000200	SEEDING, CLASS 2	ACRE	2.5	2.5	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	237	237	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	237	237	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	237	237	
25100115	MULCH, METHOD 2	ACRE	2.2	2.2	
25100630	EROSION CONTROL BLANKET	SO YD	1269	1269	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	526	526	
28000300	TEMPORARY DITCH CHECKS	EACH	15	15	
28000400	PERIMETER EROSION BARRIER	FOOT	100	100	
28100107	STONE RIPRAP, CLASS A4	SO YD	156	156	
28100205	STONE RIPRAP, CLASS A3	TON	75	75	
28200100	FILTER FABRIC FOR USE WITH RIPRAP	SO YD	266	266	
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	138	138	
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SO YD	1170	1170	
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	45	45	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.2	1.2	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SO YD	160	160	
44000006	BITUMINOUS SURFACE REMOVAL, 1.5"	SO YD	1180	1180	
44000100	PAVEMENT REMOVAL	SO YD	160	160	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	601	601	
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SO YD	800	800	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
50105200	REMOVE EXISTING CULVERTS	EACH	2	2	
50800105	REINFORCEMENT BARS	POUND	30,480	30,480	
51205200	TEMPORARY SHEET PILE	SO FT	657	657	
51500100	NAME PLATES	EACH	1	1	
54003000	CONCRETE BOX CULVERTS	CU YD	186.5	186.5	
54213453	END SECTIONS 18"	EACH	4	4	
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	80	80	
63000000	STEEL PLATE BEAM GUARD RAIL, TY. A	FOOT	225	225	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		X028-2A	
63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	31.0	31.0	
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4	
63200310	GUARD RAIL REMOVAL	FOOT	562	562	
63304385	TRAFFIC BARRIER TERMINAL REMOVAL TY. 1	EACH	4	4	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	16	16	
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	1	1	
66700605	PERMANENT SURVEY TIES	EACH	4	4	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	408	408	
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	4643	4643	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	135	135	
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4800	4800	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	16	16	
78200405	GUARDRAIL MARKERS	EACH	13	13	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	16	16	
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SO YD	2619	2619	
X4066424	BITUMINOUS CONCRETE SURFACE COURSE SUPER PAVE, MIX "D", N50	TON	545	545	
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPER PAVE, IL-19.0 N50	TON	988	988	
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	25	25	
XX003131	TEMPORARY DETOUR DRAINAGE STRUCTURE	L SUM	1	1	
Z0002600	BAR SPLICERS	EACH	121	121	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0016600	DETOUR ROADWAY REMOVAL	SO YD	2619	2619	
Z0054400	ROCK FILL	CU YD	88	88	
X4301767	RUBBLIZE PAVEMENT	SO YD	1973	1973	

* SPECIALTY ITEM

REVISOR 10-26-04