

LOCATION	STAGE I				STAGE II				STAGE III				TOTAL	FURNISH & PLACE TOP SOIL 4"
	RUN-A-ROUND BUILD-UP				MAINLINE				RUN-A-ROUND REMOVAL					
	EARTH EXCAV.	EARTH EXCAV. ADJUST. FOR SHRINKAGE(25%)	EMBANK-MENT	(-)FUR. EXC./ (+)WASTE	EARTH EXCAV.	EARTH EXCAV. ADJUST. FOR SHRINKAGE(25%)	EMBANK-MENT	(-)FUR. EXC./ (+)WASTE	EARTH EXCAV.	EARTH EXCAV. ADJUST. FOR SHRINKAGE(25%)	EMBANK-MENT	(-)FUR. EXC./ (+)WASTE		
STA. TO STA.	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	SQ YD
1008+00 TO 1008+50	1.7	1.28	0.0	1.28	1.7	1.28	0.0	1.28	0.0	1.28	0.0	0.00	0.0	0.00
1008+50 TO 1009+00	27.0	20.25	5.3	14.95	3.3	2.48	0.0	2.48	9.4	7.05	8.4	-1.35	54.96	54.96
1009+00 TO 1009+50	55.9	41.93	11.6	30.33	43.3	32.48	3.0	29.48	22.5	16.88	25.2	-8.33	180.18	180.18
1009+50 TO 1010+00	64.5	48.38	14.3	34.08	76.4	57.30	6.1	51.20	24.2	18.15	39.8	-21.65	274.96	274.96
1010+00 TO 1010+50	63.7	47.78	16.5	31.28	56.1	42.08	11.9	30.18	21.5	16.13	44.3	-28.18	328.80	328.80
1010+50 TO 1011+00	56.0	42.00	22.5	19.50	33.8	25.35	39.8	-14.45	33.8	25.35	42.1	-16.75	393.19	393.19
1011+00 TO 1011+50	43.8	32.85	32.7	0.15	20.6	15.45	88.9	-73.45	58.8	44.10	34.0	10.10	452.14	452.14
1011+50 TO 1012+00	31.7	23.78	56.8	-33.03	13.0	9.75	169.5	-159.75	92.8	69.60	23.4	46.20	488.62	488.62
1012+00 TO 1012+50	34.4	25.80	81.7	-55.90	14.4	10.80	252.1	-241.30	128.9	96.68	25.7	70.98	541.49	541.49
1012+50 TO 1013+00	47.2	35.40	99.9	-64.50	28.3	21.23	315.4	-294.18	166.2	124.65	37.0	87.65	609.66	609.66
1013+00 TO 1013+50	58.2	43.65	134.2	-90.55	50.3	37.73	368.9	-331.18	218.5	163.88	46.8	117.08	660.19	660.19
1013+50 TO 1014+00	82.6	61.95	185.0	-123.05	84.2	63.15	415.1	-351.95	283.9	212.93	68.8	144.13	746.87	746.87
1014+00 TO 1014+54	55.5	41.63	173.7	-132.08	56.8	42.60	301.7	-259.10	233.9	175.43	51.2	124.23	716.17	716.17
1014+54 TO 1015+00	45.2	33.90	155.2	-121.30	42.2	31.65	210.8	-179.15	178.6	133.95	35.2	98.75	577.99	577.99
1015+00 TO 1015+50	88.1	66.08	209.8	-143.73	71.0	53.25	263.3	-210.05	262.2	196.65	66.7	129.95	697.11	697.11
1015+50 TO 1016+00	64.6	48.45	183.4	-134.95	42.0	31.50	155.5	-124.00	242.9	182.18	52.8	129.38	618.96	618.96
1016+00 TO 1016+50	56.5	42.38	144.2	-101.83	52.1	39.08	106.7	-67.63	189.1	141.83	31.3	110.53	504.48	504.48
1016+50 TO 1017+00	69.7	52.28	63.1	-10.83	91.3	68.48	58.6	9.87	110.0	82.50	29.3	53.20	478.18	478.18
1017+00 TO 1017+50	95.1	71.33	7.4	63.93	79.3	59.48	17.8	41.68	64.9	48.68	49.8	-1.12	510.63	510.63
1017+50 TO 1018+00	100.3	75.23	5.1	70.13	105.8	79.35	3.3	76.05	54.0	40.50	57.5	-17.00	459.45	459.45
1018+00 TO 1018+50	75.3	56.48	14.7	41.78	149.6	112.20	0.0	112.20	56.2	42.15	47.2	-5.05	390.64	390.64
1018+50 TO 1019+00	40.8	30.60	25.5	5.10	69.0	51.75	0.0	51.75	49.9	37.43	26.1	11.33	241.40	241.40
1019+00 TO 1019+50	10.9	8.18	27.5	-19.33	3.6	2.70	0.0	2.70	28.6	21.45	5.1	16.35	78.15	78.15
1019+50 TO 1020+00	2.8	2.10	11.6	-9.50	3.2	2.40	0.0	2.40	6.6	4.95	0.0	4.95	12.43	12.43
1020+00 TO 1020+50	1.4	1.05	0.0	1.05	1.5	1.13	0.0	1.13	0.0	0.00	0.0	0.00		
SUB-TOTAL	1272.90	954.68	1681.70	-727.03	1192.80	894.60	2788.40	-1893.80	2537.40	1903.05	847.70	1055.35		
TOTAL FURN./ WASTE				-727.03				-1893.80				1055.35		
TOTAL EARTH EXCAV.	1272.90				1192.80				2537.40					5003
														10017

* QUANTITIES FOR FURNISHED EXCAVATION IS CALCULATED FOR STAGE I & STAGE II ONLY, NO FURNISHED EXCAVATION FOR STAGE III IS REQUIRED.

END SECTIONS 18"		
LOCATION		EACH
STA. 1016+50	36.6' LT	2.0
STA 1017+50	27.3' RT	2.0
TOTAL		4.0

STATION	MULCH METHOD 2	SEEDING, CL 2	FERTILIZER		
			NITROGEN	PHOSPHORUS	POTASSIUM
			ACRE	ACRE	POUND
1008+50 TO 1020+00	2.2	2.5	237	237	237
TOTAL	2.2	2.5	237	237	237

TEMPORARY DITCH CHECKS	
LOCATION	EACH
LT/RT STA 1013+00	2.0
LT/RT STA 1014+00	2.0
LT/RT STA 1014+50	2.0
LT/RT STA 1015+00	2.0
LT/RT STA 1015+50	2.0
RUNAROUND	
STA 1013+00	1.0
STA 1014+00	1.0
STA 1014+50	1.0
STA 1015+00	1.0
STA 1015+50	1.0
TOTAL	15.0

PIPE CULVERTS, CLASS D TYPE 1 18"		
LOCATION	SQ. YD.	
STA. 1016+50	36.9' LT	35.0
STA. 1017+50	27.6' RT	45.0
TOTAL		80.0

REMOVE EXISTING CULVERTS		
LOCATION	EACH	
STA 1016+30	22.2' LT	1.0
STA 1017+50	RT	1.0
TOTAL		2.0

TEMPORARY EROSION CONTROL SEEDING	
LOCATION	POUND
STA. 1008+50 TO STA. 1020+50	526
TOTAL	526

EROSION CONTROL BLANKET	
LOCATION	SQ. YD.
LT STA 1009+00 - 1014+50	333.8
RT STA 1009+00 - 1014+50	333.9
LT STA 1015+00 - 1019+50	300.3
RT STA 1015+00 - 1019+50	300.7
(AREAS MEASURED IN CADD)	
TOTAL	1269

PERIMETER EROSION CONTROL	
LOCATION	FOOT
MAIN LINE	
LT, RT STA. 1014+53	100
TOTAL	100

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 SCALE: VERT. DATE
 HORIZ. DATE
 DRAWN BY
 CHECKED BY