

SCHEDULE OF QUANTITIES

INTERCHANGES

FROM STATION	TO STATION	PAVEMENT SLOPE (%)	DRAIN SLOPE (%)	PIPE UNDERDRAINS, 4"				PIPE UNDERDRAINS, 4" (SPECIAL)				CONCRETE HEADWALLS FOR PIPE UNDERDRAINS (EACH)	SHLOULDER REMOVAL & REPLACEMENT, 11"				SHLOULDER REMOVAL & REPLACEMENT, 11"			
				NORTHBOUND		SOUTHBOUND		NORTHBOUND		SOUTHBOUND			NORTHBOUND		SOUTHBOUND		NORTHBOUND		SOUTHBOUND	
				OUTSIDE (FT)	MEDIAN (FT)	OUTSIDE (FT)	MEDIAN (FT)	OUTSIDE (FT)	MEDIAN (FT)	OUTSIDE (FT)	MEDIAN (FT)		OUTSIDE (FT)	MEDIAN (FT)	OUTSIDE (FT)	MEDIAN (FT)	OUTSIDE (FT)	MEDIAN (FT)	OUTSIDE (FT)	MEDIAN (FT)
I-57/US 45 INTERCHANGE																				
RAMP A																				
522+00				0	0	0	0	20	0	0	0	1	0	0	0	0	9.5	0	0	0
522+00	526+20	+0.48	PGL	420	0	0	0	20	0	0	0	1	420	0	0	0	9.5	0	0	0
RAMP B																				
487+00	5+00	+0.48	PGL	500	0	0	0	20	0	0	0	1	500	0	0	0	9.5	0	0	0
5+00	8+13	+0.48	PGL	313	0	0	0	0	0	0	0	0	313	0	0	0	0	0	0	0
RAMP C																				
85+00				0	0	0	0	0	0	20	0	1	0	0	0	0	0	0	9.5	0
85+00/487+00(157)	80+00	+0.2	+0.4	0	0	500	0	0	0	20	0	1	0	0	500	0	0	0	9.5	0
80+00	75+00	+0.2	+0.4	0	0	500	0	0	0	0	0	0	0	0	500	0	0	0	9.5	0
RAMP D																				
3+00				0	0	0	0	0	0	20	0	1	0	0	0	0	0	0	9.5	0
3+00/522+00(I-57)	526+00	+0.48	PGL	0	0	400	0	0	0	20	0	1	0	0	400	0	0	0	9.5	0
I-57/IL 16 INTERCHANGE																				
RAMP B																				
767+00	72+00/772+00(I-57)	+0.21	+0.4	500	0	0	0	20	0	0	0	1	500	0	0	0	9.5	0	0	0
72+00	76+00	+0.21	+0.4	400	0	0	0	20	0	0	0	1	400	0	0	0	9.5	0	0	0
76+00	78+02	+0.21	+0.4	202	0	0	0	0	0	0	0	0	202	0	0	0	0	0	0	0
RAMP D																				
767+00	63+50/770+50(I-57)	+0.21	+0.4	0	0	350	0	0	0	20	0	1	0	0	350	0	0	0	9.5	0
63+50	60+00	+0.21	+0.4	0	0	350	0	0	0	20	0	1	0	0	350	0	0	0	9.5	0
60+00	55+00	+0.21	+0.4	0	0	500	0	0	0	0	0	0	0	0	500	0	0	0	0	0
RAMP F																				
9+00	6+00	-1.99	PGL	0	0	300	0	0	0	20	0	1	0	0	300	0	0	0	9.5	0
6+00	807+10	-1.99	PGL	0	0	310	0	0	0	20	0	1	0	0	310	0	0	0	9.5	0
SHEET TOTALS:				2335.0	0	3210.0	0	100.0	0	160.0	0	13	2335.0	0	3210.0	0	47.5	0	85.5	0
JOB TOTALS:				32117.0	34537.0	33256.0	34537.0	1510.0	1540.0	1560.0	1540.0	291.0	32117.0	34537.0	33256.0	34537.0	674.5	267.5	712.5	267.5