

SUMMARY OF QUANTITIES

SHEET 2 OF 2

LOCATION OF WORK: FAP 332
ILL ROUTE 1
RURAL
STA. 591+10
TO
STA. 600+10
S. N. 012-0071
80% FED
20% STATE

CONSTRUCTION TYPE CODE: X081-2A

CODE NO	ITEM	UNIT	TOTAL QUANTITY
54215547	METAL END SECTIONS 12"	EACH	2.0
60100945	PIPE DRAINS 12"	FOOT	75.0
60900240	TYPE C INLET BOX, STANDARD 609006	EACH	2.0
60900515	CONCRETE THRUST BLOCKS	EACH	2.0
• 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	575.0
• 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4.0
• 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4.0
• 63301000	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL	FOOT	2,282.0
66411900	TEMPORARY FENCE	FOOT	234.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4.0
67100100	MOBILIZATION	L SUM	1.0
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1.0
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1.0
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	2.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	147.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	49.0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	540.0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	540.0
• 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1,652.0
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	19.0
• 78200400	GUARDRAIL REFLECTORS	EACH	14.0
• 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	19.0
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	2.0
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N70	TON	221.0
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	834.0
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1.0
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1.0
• 70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1.0
Z0002600	BAR SPLICERS	EACH	658.0
Z0002900	BASE COURSE (OPTION)	SQ YD	598.0
•• Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 2	EACH	2.0
•• Z0030340	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 2	EACH	2.0
Z0038700	PERMANENT BENCH MARKS	EACH	1.0
Z0065000	SETTING PILES IN ROCK	EACH	12.0

• = SPECIALTY ITEMS
•• = SAFETY - 3N

REVISED
JAN 07 2005