

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	024BR-1BR	CLARK	50	9

CONTRACT NO. 70218

SCHEDULE OF QUANTITIES**SHEET 2 OF 2****TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT) - 63100167**

STATION	QUANTITY (EACH)
LT 592+08.31	1.0
RT 591+20.81	1.0
LT 599+99.39	1.0
RT 599+11.89	1.0
TOTAL = 4.0 EACH	

TRAFFIC BARRIER TERMINAL, TYPE 6 - 63100085

STATION	QUANTITY (EACH)
LT 594+77.06	1.0
RT 594+77.06	1.0
LT 596+43.14	1.0
RT 596+43.14	1.0
TOTAL = 4.0 EACH	

REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL - 63301000**REMOVE**

STATION	TO	STATION	LENGTH (FT)
SW 596+91.67	---	600+31.07	340.00
NW 593+95.33	---	594+96.33	101.00
NE 593+94.33	---	594+96.33	102.00
SE 596+91.67	---	597+92.67	101.00
TOTAL =			644.0 FOOT

RE-ERECT

STATION	TO	STATION	LENGTH (FT)
SW 596+91.67	---	600+31.07	340.00
NW 593+95.33	---	594+96.33	101.00
NE 593+94.33	---	594+96.33	102.00
SE 596+91.67	---	597+92.67	101.00
TOTAL =			644.0 FOOT

REMOVE

STATION	TO	STATION	LENGTH (FT)
SW 596+91.67	---	600+31.07	340.00
NW 593+95.33	---	594+96.33	101.00
NE 593+94.33	---	594+96.33	102.00
SE 596+91.67	---	597+92.67	101.00
TOTAL =			644.0 FOOT

RE-ERECT

STATION	TO	STATION	LENGTH (FT)
SW 596+99.39	---	598+61.39	162.50
NW 593+95.81	---	594+45.81	50.00
NE 593+95.81	---	594+45.81	50.00
SE 596+99.39	---	597+86.89	87.50
TOTAL =			350.0 FOOT

PAINT PAVEMENT MARKING LINE - 4" - 78001110

STATION	TO	STATION	LENGTH (FT)
591+02.00	---	594+77.06	375.10
596+43.14	---	600+18.00	374.90
TOTAL =			749.9 FOOT
749.9' X 25% =			187.5 FOOT
TOTAL =			188.0 FOOT