

SUMMARY OF QUANTITIES

LOCATION OF WORK:

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CUMBERLAND COUNTY		
				QUANTITY	QUANTITY	QUANTITY
67100100	MOBILIZATION	L SUM	1.0	0.33	0.33	0.34
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	0.33	0.33	0.34
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1.0	1.0		
80500100	SERVICE INSTALLATION, TYPE A	EACH	2.0		1.0	1.0
80500200	SERVICE INSTALLATION, TYPE B	EACH	1.0	1.0		
80802000	WOOD POLE, 35 FT., CLASS 3	EACH	5.0	1.0	2.0	2.0
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	385.0	385.0		
81021540	CONDUIT, AUGERED 1 1/2" DIA., PVC	FOOT	322.0	322.0		
81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., GALVANIZED STEEL	FOOT	48.0	48.0		
81400100	HANDHOLE	EACH	1.0	1.0		
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	385.0	385.0		
85800100	FLASHER CONTROLLER	EACH	3.0	1.0	1.0	1.0
86600010	GULFBOX JUNCTION	EACH	1.0	1.0		
87200400	SPAN WIRE	FOOT	193.0		101.0	92.0
87200500	TETHER WIRE	FOOT	193.0		101.0	92.0
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	889.0	889.0		
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	67.0	41.0	13.0	13.0
87302225	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 3C	FOOT	165.0		82.0	83.0
89502400	REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE	EACH	3.0	1.0	1.0	1.0
X7012620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	EACH	1.0	1.0		
X8801100	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 1-SECTION, POST MOUNTED	EACH	4.0	4.0		
X8801505	SIGNAL HEAD, POLYCARBONATE, LED, 4-FACE, 1-SECTION, SPAN WIRE MOUNTED	EACH	4.0		2.0	2.0

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	6	3

CONTRACT NO. 70439
 * FAP 91 & FAS 1707
 ** D5 HES 2005-6
 *** COLES & CUMBERLAND