

LIGHTING SYSTEM		
LOCATION	REMOVAL AND SALVAGE LUMINAIRE (EACH)	NEW LUMINAIRE * (EACH)
<u>VIETNAM VETERANS MEMORIAL</u>		
STA 10+37.12 - 50.15' LT	1	
STA 10+37.50 - 37.50' LT	1	
STA 10+42.19 - 54.18' LT	1	
STA 10+42.34 - 34.72' LT	1	
STA 10+42.96 - 42.07' LT		1
STA 10+42.96 - 46.98' LT		1
STA 10+46.87 - 34.82' LT		1
STA 10+46.87 - 54.02' LT		1
STA 10+51.54 - 35.17' LT		1
STA 10+51.56 - 54.38' LT		1
STA 10+54.20 - 39.24' LT	1	
STA 10+54.36 - 51.15' LT	1	
* THIS ITEM TO BE PAID FOR AS LIGHTING SYSTEM COMPLETE (L SUM)		
TOTAL =	6	6

GRANITE AGGREGATE CONCRETE	
LOCATION	QUANTITY (SQ FT)
<u>LINCOLN MEMORIAL DRIVE</u>	
STA 13+35.38 - 45.88' RT	555.0
TOTAL =	555

SIGNING SCHEDULE					
LOCATION:	MUTCD NO.	MESSAGE	SIZE IN x IN	SIGN PANELS T-1 (SQ FT)	TELE. SIGN SUPPORT (FOOT)
<u>VIETNAM VETERANS MEMORIAL PARKING LOT :</u>					
STA 14+51.25 RT OFFSET 32.00'	R7-8	HANDICAP PARKING	12 x 18	1.50	17.0
	R7-I101	\$100 FINE	6 x 12	0.50	
STA 14+60.50 RT OFFSET 32.00'	R7-8	HANDICAP PARKING	12 x 18	1.50	17.0
	R7-I101	\$100 FINE	6 x 12	0.50	
STA 15+08.61 RT OFFSET 32.00'	R7-8	HANDICAP PARKING	12 x 18	1.50	17.0
	R7-I101	\$100 FINE	6 x 12	0.50	
STA 15+23.04 RT OFFSET 32.00'	R7-8	HANDICAP PARKING	12 x 18	1.50	17.0
	R7-I101	\$100 FINE	6 x 12	0.50	
<u>KOREAN WAR MEMORIAL PARKING LOT :</u>	R7-8	HANDICAP PARKING	12 x 18	3.00	17.0
	R7-I101	\$100 FINE	6 x 12	1.00	
(SEE PLANS FOR LOCATIONS)					
TOTAL =				12.00	85.0

NOTES: ALL POST UNLESS OTHERWISE NOTED SHALL MEET THE REQUIREMENTS OF SECTION 728 OF THE STANDARD SPECIFICATIONS. EACH POST SHALL ALSO INCLUDE A 2 1/4" x 2 1/4" x 4' BASE DRIVEN INTO THE GROUND EXCEPT THE LAST 2".

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 SCALE: VERT. _____
 DATE _____ HORIZ. _____
 DRAWN BY _____
 CHECKED BY _____