

CKT
10/26/04
\\74034c\d01904pa.dgn

90% FED.
5% STATE
5% CITY

SUMMARY OF QUANTITIES

90% FED.
5% STATE
5% CITY

| | | | | |
|-----------------------|---------|-----------|--------------|----------------------|
| FAP NO. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 821 | 13TS-2 | JEFFERSON | 8 | 3 |
| FED. ROAD DIST. NO. 7 | | ILLINOIS | | FED. AID PROJECT NO. |
| CONTRACT NO. 74034 | | | | |

| SUMMARY OF QUANTITIES | | | URBAN TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | |
|-----------------------|--|-------|------------------------|------------------------|--|--|
| CODE NO | ITEM | UNIT | | Y031-1F | | |
| 42400100 | PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH | SQ FT | 260 | 260 | | |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 34 | 34 | | |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 152 | 152 | | |
| 60605100 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT) | FOOT | 34 | 34 | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | |
| 70102632 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701602 | L SUM | 1 | 1 | | |
| 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1 | 1 | | |
| * 72000200 | SIGN PANEL - TYPE 2 | SQ FT | 48 | 48 | | |
| * 78005100 | EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 94 | 94 | | |
| * 78005110 | EPOXY PAVEMENT MARKING - LINE 4" | FOOT | 277 | 277 | | |
| * 78005130 | EPOXY PAVEMENT MARKING - LINE 6" | FOOT | 190 | 190 | | |
| * 78005180 | EPOXY PAVEMENT MARKING - LINE 24" | FOOT | 150 | 150 | | |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 228 | 228 | | |
| 81012600 | CONDUIT IN TRENCH, 2" DIA., PVC | FOOT | 155 | 155 | | |
| 81013000 | CONDUIT IN TRENCH, 4" DIA., PVC | FOOT | 101 | 101 | | |
| 81021590 | CONDUIT, AUGERED 4" DIA., PVC | FOOT | 275 | 275 | | |
| 81100600 | CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL | FOOT | 10 | 10 | | |
| 81400100 | HANDHOLE | EACH | 3 | 3 | | |
| 81400300 | DOUBLE HANDHOLE | EACH | 1 | 1 | | |
| 81500200 | TRENCH AND BACKFILL FOR ELECTRICAL WORK | FOOT | 256 | 256 | | |
| 85700200 | FULL-ACTUATED CONTROLLER AND TYPE IV CABINET | EACH | 1 | 1 | | |
| 87301215 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C | FOOT | 473 | 473 | | |
| 87301235 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 4C | FOOT | 494 | 494 | | |
| 87301245 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C | FOOT | 1481 | 1481 | | |
| 87301255 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C | FOOT | 823 | 823 | | |
| 87301805 | ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C | FOOT | 21 | 21 | | |
| 87502660 | TRAFFIC SIGNAL POST, ALUMINUM 12 FT. | EACH | 1 | 1 | | |
| 87502680 | TRAFFIC SIGNAL POST, ALUMINUM 14 FT. | EACH | 1 | 1 | | |
| 87502700 | TRAFFIC SIGNAL POST, ALUMINUM 16 FT. | EACH | 1 | 1 | | |
| 87702930 | COMBINATION STEEL MAST ARM ASSEMBLY AND POLE, 40 FT. | EACH | 1 | 1 | | |

| SUMMARY OF QUANTITIES | | | URBAN TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | |
|-----------------------|---|------|------------------------|------------------------|--|--|
| CODE NO | ITEM | UNIT | | Y031-1F | | |
| 87702950 | COMBINATION STEEL MAST ARM ASSEMBLY AND POLE, 44 FT. | EACH | 1 | 1 | | |
| 87702960 | COMBINATION STEEL MAST ARM ASSEMBLY AND POLE, 46 FT. | EACH | 2 | 2 | | |
| 87800100 | CONCRETE FOUNDATION, TYPE A | FOOT | 9 | 9 | | |
| 87800200 | CONCRETE FOUNDATION, TYPE D | FOOT | 3.5 | 3.5 | | |
| 87800415 | CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER | FOOT | 52 | 52 | | |
| 88200410 | TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC | EACH | 15 | 15 | | |
| 88800100 | PEDESTRIAN PUSH-BUTTON | EACH | 2 | 2 | | |
| 89502400 | REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE | EACH | 1 | 1 | | |
| X0320872 | VIDEO VEHICLE DETECTION SYSTEM | EACH | 1 | 1 | | |
| X0320903 | CIRCUIT BREAKER AND ENCLOSURE | EACH | 1 | 1 | | |
| X8801300 | SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED | EACH | 3 | 3 | | |
| X8801310 | SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED | EACH | 8 | 8 | | |
| X8801395 | SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED | EACH | 2 | 2 | | |
| X8801400 | SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED | EACH | 2 | 2 | | |
| X8810397 | PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 2-SECTION BRACKET MOUNTED | EACH | 2 | 2 | | |

* SPECIALTY ITEMS

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SCALE: VERT. DATE
HORIZ. DATE
DRAWN BY
CHECKED BY