

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	1000-2A	1000-2A	Y031-1F	PARKING LANES	X020-2A	Y030-1E
				4 LANE	2 LANE	TRAFFIC SIGNALS	BOX CULVERT	HIGHWAY	
				100% STATE	100% STATE	IL 162 @ RIGGIN RD.	50% STATE 50% CITY	SN 060-0403	LIGHTING
						90% STATE 10% CITY	Y025	100% STATE	100% STATE
X032A748	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 66"	FOOT	126						
X4009132	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90 11.5"	SQ YD	16,377	14,711	1,666				
XX002154	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3V FRAME AND GRATE	EACH	4	4					
XX001875	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3V FRAME AND GRATE	EACH	6	6					
XX002155	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 3V FRAME AND GRATE	EACH	17	11	6				
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1490		1490				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	837		837				
20100500	TREE REMOVAL, ACRES	ACRE	1.1		1.1				
20200100	EARTH EXCAVATION	CU YD	44,377	7232	37145				
20800150	TRENCH BACKFILL	CU YD	7721	6856	865				
20900310	POROUS GRANULAR BACKFILL	TON	14				14		
25000110	SEEDING, CLASS 1A	ACRE	3.8	3.4	0.4				
25000200	SEEDING, CLASS 2	ACRE	12.5		12.5				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1465	317	1148				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1465	317	1148				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1465	317	1148				
25100115	MULCH, METHOD 2	ACRE	16.3	3.5	12.8				
25100630	EROSION CONTROL BLANKET	SQ YD	5491	143	5348				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1628	353	1275				
28000300	TEMPORARY DITCH CHECKS	EACH	268	19	249				
28000400	PERIMETER EROSION BARRIER	FOOT	4335	2580	1755				
28000500	INLET AND PIPE PROTECTION	EACH	36	25	11				
28100107	STONE RIPRAP, CLASS A4	SQ YD	25		25				
28200100	FILTER FABRIC FOR USE WITH RIPRAP	SQ YD	25		25				
30200400	PROCESSING LIME MODIFIED SOIL 12"	SQ YD	24,336	21,659	2,677				
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	3279	1619	1,660				
30201500	LIME	TON	467	416	51				
35300705	PORTLAND CEMENT CONCRETE BASE COURSE 12 1/4"	SQ YD	3127	3127					
30201400	WATER	UNIT	366	299	67				
40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	261	22	239				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	26	11.8	13		1.2		
40600300	AGGREGATE (PRIME COAT)	TON	124.6	56.9	62.1		5.6		
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	231	151	80				
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	104	104					

7/1/2004 1:46:07 PM C:\p\proj\60R-2,3TR-1\60R-2,3TR-1.dgn L:\1-63

Rev.