FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
586	60R-2,37R-1	MADISON	502	30
STA.		TO STA.		
CONTRACT NO: 76301				

STORM SEWER AND PIPE CULVERT SCHEDULE

POINT	SLOPE	STORM SEWER CLASS A (FOOT)														PIPE CULVERTS CLASS A (FOOT)		PIPE CULVERTS, CLASS A, (FOOT)					PIPE CULVERTS, CLASS D, (FOOT)							TRENCH BACKFILL (CU YD)	STORM SEWERS WATER MAIN QUALITY PIPE (FOOT)					STORM SEWER (WATER MAIN REQUIREMENTS) (FOOT)			
		12"		15"		18"	24"	30"	36"	42"		48"	60"		66"	15"	18"	TYPE 1			TYPE 2		TYPE 1								12"		15"	24"	66"	18"	21"	36"	42"
		TY 1	TY 2	TY 1	TY 2	TY 2	TY 2	TY 2	TY 2	TY 2	TY 3	TY 3	TY 2	TY 3	TY 2			12"	15"	18"	15"	60"	12"	15"	18"	21"	24"	30"	60"		TY 1	TY2	TY 1	TY2	TY2				
1L - 2L	0.73%																													0.7			45						
2L - 3L	0.12%																													29.3	215								
3L - 4L	0.12%	8																												0.5									
1R - 2R	1.00%				28																									0.4									
3R - 4R	1.00%				28																									0.4									
5R - 6R	0.79%			71																										0.0									
7L - 8L	-0.45%	8																												1.6									
8L - 9L	-0.45%	369																												74.4									
9L - EX	-2.40%			58																										16.6									
7R - 8R	-0.50%															69														0.0									
9R - 10R	-0.50%															53														0.0									
11R - 12R	-0.50%																61													0.0									
13R - 14R	-0.44%	8																												1.7									
14R - 15R	-0.44%	223																												47.1									
15R - 16R	-0.26%	206																												64.1									
16R - EX	7.20%	20																												2.7									
EX - 11L	2.27%																													39.9							42		
11L - 12L	1.64%																													7.2							6		
12L - 13L	1.64%																													99.3						279			
EX - 17R	2.74%		53																											36.5									
17R - 18R	2.74%		8																											6.7									
18R - 19R	2.74%		80																											24.5									
19R - 20R	1.00%		199																											44.0									
EX - 21R	2.74%					144																								0.0									
21R - 22R	1.00%					199																								0.0									
14L - 23R	1.00%		68																											16.0									
23R - 24R	1.00%		16																											0.5									
23R - 25R	-0.42%					237																								92.6									
25R - 26R	1.00%																													0.9	35								
25R - 27R	-0.82%						196																							121.4									
27R - 28R	-0.75%							146																						101.4									
28R - 29R	-0.87%								196																					138.9									
29R - 30R	10.00%																													0.6	10								
15L - 25R	3.83%																													12.8		68							
16L - 27R	1.00%	66																												15.1									
17L - 18L	1.00%																													0.2		20							
18L - 28R	1.00%		68																											20.0									

STORM SEWER AND PIPE CULVERT SCHEDULE CONTINUED ON NEXT SHEET

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STORM SEWER &
PIPE CULVERT SCHEDULE

FAP ROUTE 586 (IL 162)
SECTION 60R-2,37R-1
MADISON COUNTY

DRAWN BY:

PLOT DATE: Wednesday December 01, 2004 @ 1:56:17 PM

PLAN
SCRIBED
PLOTTED
ALIGNMENT CHECKED
PLAN/PROFILE CHECKED
CADD FILE NAME
NOTE BOOK
NO.
BY
DATE

12/1/2004
Wednesday December 01, 2004 @ 1:56:17 PM
c:\projects\ed16919\plan\pl-8@60ogdn LV:1:63