

PATCHING SCHEDULE							
LOCATION	LT	RT	LENGTH	WIDTH	TYPE 2 SQ YD	TYPE 3 SQ YD	TYPE 4 SQ YD
542+20	X		19	6	12.7		
542+20		X	19	6	12.7		
542+50	X		19	6	12.7		
544+20	X		19	6	12.7		
544+20		X	19	6	12.7		
545+70	X		19	6	12.7		
545+70		X	19	6	12.7		
547+70	X		19	6	12.7		
547+70		X	19	6	12.7		
549+75	X		19	8		16.9	
549+90	X		19	6	12.7		
549+90		X	19	6	12.7		
554+60	X		19	6	12.7		
554+60		X	19	6	12.7		
558+50	X		19	6	12.7		
558+50		X	19	6	12.7		
DIANA		X	26	6		17.3	
566+70	X		16	6	10.7		
566+70		X	19	6	12.7		
LAUNDRY		X	23	6		15.3	
570+50	X		13	6	8.7		
571+40	X		13	6	8.7		
571+40		X	13	6	8.7		
572+50	X		13	6	8.7		
572+50		X	13	6	8.7		
572+75	X		13	6	8.7		
573+60	X		13	6	8.7		
573+60		X	13	6	8.7		
SARAH		X	90	6			60.0
575+50	X		13	6	8.7		
575+50		X	13	6	8.7		
575+90	X		13	6	8.7		
575+90		X	13	6	8.7		
WICKLIFFE		X	40	6			26.7
578+50	X		13	6	8.7		
578+50		X	13	6	8.7		
579+50	X		13	6	8.7		
579+50		X	13	6	8.7		
579+64	X		13	6	8.7		
579+64		X	13	6	8.7		
579+75	X		13	6	8.7		
BORDER	X		20	6	13.3		
586+25	X		24	6		16.0	
583+25		X	24	6		16.0	
611+75	X		12	6	8.0		
611+75		X	12	6	8.0		
612+75	X		12	6	8.0		
612+75		X	12	6	8.0		
621+75	X		12	6	8.0		
621+75		X	12	6	8.0		
630+25	X		12	6	8.0		
630+25		X	12	6	8.0		
631+75	X		12	6	8.0		
631+75		X	12	6	8.0		
650+92	X		8	12	10.7		
650+92		X	8	12	10.7		
663+08	X		6	12	8.0		
663+08		X	6	12	8.0		
674+75	X		12	12		16.0	
674+75		X	12	12		16.0	
686+17	X		6	12	8.0		
686+17		X	6	12	8.0		
696+06	X		6	12	8.0		
696+06		X	6	12	8.0		
US 40	X		20	12			26.7
US 40		X	20	12			26.7
SUB-TOTAL					540.7	113.6	140.0
25% ANTICIPATED					135	30	35
TOTAL					675.7	143.6	175.0

CURB & GUTTER AND MEDIAN SCHEDULE

LOCATION	COMB CONC C & G TY B6.24 FOOT	COMB CONC C & G TY B6.12 FOOT	COMB CONC C & G TY M6.06 FOOT	COMB CONC C & G TY M6.24 FOOT	CONC CURB TYPE B FOOT	CONC MEDIAN SURFACE, 4" SQ YD
LEFT						
508+15 - 518+65	1176					
531+96 - 535+24	417					
535+24 - 546+21	1226					
546+21 - 550+75	479					
550+75 - 556+70	122	688				
556+70 - 574+95	2018					
574+95 - 581+56	868					
581+56 - 582+70	150					
RIGHT						
508+06 - 518+65	1493					
531+96 - 550+75	2213					
550+75 - 561+70	1250					
561+70 - 567+58	647					
567+58 - 574+00	713					
574+00 - 577+92	401					
577+92 - 580+97	502	54				
580+97 - 581+43	162					
581+43 - 582+70	0				51	
MEDIAN						
507+90 - 509+14	230					52
548+78 - 550+15			128	128		30
551+27 - 552+72			138	138		35
RIGGIN RD						
7+00 - 9+62 (LT)	406					
7+00 - 9+62 (RT)	353					
SW RAMPS						
TOTALS	14826	742	266	266	113	117

SHOULDER SCHEDULE

LOCATION STA. - STA.	SIDE (LT/RT)	BITUMINOUS SHOULDER SUPERPAVE, 8" (SQ YD)	AGGREGATE SHOULDER TYPE A, 6" (SQ YD)
IL 162 (CENTER ST)			
STA 608+00 - STA 613+60	LT	233.3	
STA 608+00 - STA 618+25	RT	472.7	
STA 613+60 - STA 622+75	LT	406.7	373.7
STA 618+25 - STA 627+50	RT	411.1	357.3
STA 622+75 - STA 632+50	LT	541.7	
STA 627+50 - STA 633+85	RT	352.8	
STA 632+50 - STA 719+33	LT	3818.7	3685.8
STA 633+85 - STA 703+00	RT	2968.8	2852
STA 703+00 - STA 705+85	RT	158.3	
STA 705+85 - STA 713+75	RT	351.1	341.7
STA 713+75 - STA 717+75	RT	222.2	
STA 717+75 - STA 719+33	RT	76.4	76.4
TOTAL		10013.8	7686.9

SIDEWALK REMOVAL SCHEDULE

LOCATION	LT/RT	LENGTH	WIDTH	SQ FT
550+26 TO 550+44	LT	44	4	176
550+94 TO 551+37	LT	107	4	428
550+37 TO 550+61	RT	64	4	256
570+29 TO 570+38	LT	10	3.5	35
573+66 TO 573+88	LT	28	3	84
574+77 TO 575+12	LT	39	4	156
577+39 TO 577+64	RT	27	4	108
578+94 TO 580+41	RT	100	4	400
581+00 TO 581+32	LT	30	4	120
581+57 TO 582+70	LT	108	4	432
581+73 TO 582+04	RT	34	7	238
535+00	LT	5	4	20
TOTAL				2453

PROTECTIVE COAT SCHEDULE

LOCATION	COMB CONC C & G / CURB SQ YD	CONC MEDIAN SURFACE SQ YD	CONC GUTTER TYPE A SQ YD
LEFT			
508+15 - 518+65	405		
531+96 - 535+24	144		
535+24 - 546+21	422		
546+21 - 550+75	165		
550+75 - 556+70	279		
556+70 - 574+95	695		
574+95 - 581+56	299		
581+56 - 582+70	52		
608+00 - 609+25			34
609+25 - 615+00			191
621+00 - 627+00			218
RIGHT			
508+06 - 518+65	514		
531+96 - 550+75	762		
550+75 - 561+70	431		
561+70 - 567+58	223		
567+58 - 574+00	246		
574+00 - 577+92	138		
577+92 - 580+97	192		
580+97 - 581+43	56		
581+43 - 582+70	18		
608+00 - 609+25			55
609+25 - 615+00			219
615+00 - 621+00			140
627+00 - 633+00			248
633+00 - 639+00			38
698+00 - 704+00			35
BETHANY LANE	24		
MEDIAN			
507+90 - 509+14	79	52	
548+78 - 550+15	88	30	
551+27 - 552+72	95	35	
RIGGIN RD			
7+00 - 9+62 (LT)	140		
7+00 - 9+62 (RT)	122		
SW RAMPS			
TOTALS	5610	117	1178
6905			

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
MISCELLANEOUS SCHEDULES
 FAP ROUTE 586 (IL 162)
 SECTION 60R-2,37R-1
 MADISON COUNTY

DRAWN BY:

PLAN NO. _____
 DATE _____
 BY _____
 CHECKED _____
 DATE _____

7/2/2004 8:32:00 AM
 C:\p04\586\60R-2,37R-1\plan\misc\misc.dgn LVH-ES