FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
586	60R-2, 37R-1	MADISON	502	70
STA. 621+00		TO STA. 627+00		
CONTRACT NO.: 76301				

PI STA. = 625+68.74
Δ = 31° 29′ 06″ (LT)
D = 3° 23′ 01″
R = 1,693.30′
T = 477.32′
L = 930.50′
E = 65.99′
e = _____
T.R. = _____
S.E. RUN = _____
P.C. STA = 620+91.42
P.T. STA = 630+21.92

MATCHLINE 621+00

MATCHLINE 627+00

TRAF. BAR. TERM. TYPE 1, SPECIAL (TAN)

CONSTR. LIMITS

EXIST. R/W

+31.7 BIT C.E. 24.0

SPBGR, TYPE A

12.5' x 10.0' CULVERT

+75 BEGIN TYPE "A" GUTTER

TRAF. BAR. TERM. TYPE 1, SPECIAL (TAN)

TEMP. ESMT.

416 E. CENTER ST

ROCK

PARKING

OAC OAKRIDGE

+406 BIT C.E. 30.0

+61.5 BIT SR 26.0

EXIST. R/W

CONSTR. LIMITS

TYPE "A" GUTTER

5' BIT. SHLDR.

621 622 623 624 ℄ RTE. 162 625+00 626

12' 12' 12' 12'

4" BIT. SHLDR.
4' AGGR. SHLDR.

+21.6 AGG P.E. 12"

8" BIT. SHLDR.
4' AGGR. SHLDR.

R 40

18" RCP

+24.6 SR 24 BIT 32.0

BIT CREEKSIDE

CONSTR. LIMITS

PROP. R/W

CONSTR. LIMITS

EXIST. R/W

PROP. R/W

TRAF. BAR. TERM. TYPE 1, SPECIAL (TAN)

TEMP. ESMT.

EXIST. R/W

AREA1=TREE REMOVAL (ACRE)

AREA2=TREE REMOVAL (ACRE)

STA. +01.97 OFF. 58.36

STA. +01.77 OFF. 25.78

STA. +18.00 OFF. 25.14

STA. +21.84 OFF. 58.87

STA. +42.49 OFF. 58.51

STA. +41.16 OFF. 22.58

STA. +61.37 OFF. 54.79

STA. +97.14 OFF. 62.93

STA. +04.99 OFF. 54.40

STA. +91.36 OFF. 21.51

DENSE TREES

ROCK

DENSE TREES

BIT

WV

TREE REMOVAL (ACRES)

20′ 0 20′ 40′
SCALE: 1" = 20′

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

PLAN VIEW

FAP 586
SECTION 60R-2, 37R-1
MADISON COUNTY

DRAWN BY:

PLOT DATE: Thursday July 01, 2004 @ 2:04:48 PM

PLAN	SCRIBED	BY	DATE
	DETAILED		
	ALIGNMENT CHECKED		
NOTE BOOK	PLAN OF RWY CHECKED		
MK.	PROFILE NAME		

7/1/2004
Thursday July 01, 2004 @ 2:04:48 PM
o:\projects\ed6993a\plan\plan848a.dgn LM:1.63

o:\projects\ed6993a\plan\236ab01_ref LM:1.59
O:\projects\ref\rf11d03x.dgn LM:2.4-15.1;7.2R,22.24-25,27-29,35,37-40,42,44,46-48,50-53,57-59