

RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2667	02-00165-00-RP	DUPAGE	87	3
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		

FUNDING BREAKDOWN	PARTICIPATING	SEQ 1	SEQ 2	NON-PARTICIPATING
		PARTICIPATING	PARTICIPATING	
LOCATION OF WORK		CHURCH RD AT GRAND AV		07C
	ROADWAY	TRAFFIC SIGNALS	SYSTEM INTERCONNECT	ELMURST

SUMMARY OF QUANTITIES		UNIT	TOTAL	SEQ 1			SEQ 2
CODE NO.	PAY ITEM			J000-2A	Y031-1F	Y031-1F	J000-2A
20101000	TEMPORARY FENCE	FOOT	200	100			100
20101100	TREE TRUNK PROTECTION	EACH	13	6			7
20101200	TREE ROOT PRUNING	EACH	5	3			2
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	8	5			3
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	3	2			1
20200100	EARTH EXCAVATION	CU YD	11,107	7,016			4,091
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	6,247	3,895			2,352
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	4,843	2,843			2,000
20800150	TRENCH BACKFILL	CU YD	447	357			90
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	18,518	13,204			5,314
21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	150	100			50
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	228	162			66
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	228	162			66
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	228	162			66
25200110	SODDING, SALT TOLERANT	SQ YD	18,518	13,204			5,314
25200200	SUPPLEMENTAL WATERING	UNIT	111	79			32
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	189	135			54
28000300	TEMPORARY DITCH CHECKS	EACH	20	20			
28000400	PERIMETER EROSION BARRIER	FOOT	1,289	1,289			
28000500	INLET AND PIPE PROTECTION	EACH	12	12			
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	150	150			
40600300	AGGREGATE (PRIME COAT)	TON	2	2			
42000311	PORTLAND CEMENT CONCRETE PAVEMENT 8 1/2" (JOINTED)	SQ YD	27,334	17,550			9,784
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	3,576	1,875			1,701
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4,736	318			4,418
44000100	PAVEMENT REMOVAL	SQ YD	32,898	21,197			11,701
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	4,344	2,157			2,187
44000300	CURB REMOVAL	FOOT	940	616			324
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	14,382	8,984			5,398
44000600	SIDEWALK REMOVAL	SQ FT	3,588	309			3,279
44201749	CLASS D PATCHES, TYPE 1, 9 INCH	SQ YD	55	55			
55037800	STORM SEWERS TO BE CLEANED 12"	FOOT	595				595
55038000	STORM SEWERS TO BE CLEANED 18"	FOOT	740				740
55038200	STORM SEWERS TO BE CLEANED 24"	FOOT	763				763
55038400	STORM SEWERS TO BE CLEANED 30"	FOOT	1,718				1,718
55038600	STORM SEWERS TO BE CLEANED 36"	FOOT	1,104				1,104
55038700	STORM SEWERS TO BE CLEANED 42"	FOOT	688				688
55038800	STORM SEWERS TO BE CLEANED 48"	FOOT	1,604				1,604
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	320	271			49
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	322	81			241
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	6	6			
55100300	STORM SEWER REMOVAL 8"	FOOT	36	36			
55100500	STORM SEWER REMOVAL 12"	FOOT	228	148			80
55100700	STORM SEWER REMOVAL 15"	FOOT	4	4			
55100900	STORM SEWER REMOVAL 18"	FOOT	4	4			
55101200	STORM SEWER REMOVAL 24"	FOOT	5				5
55101400	STORM SEWER REMOVAL 30"	FOOT	13	8			5
55101600	STORM SEWER REMOVAL 36"	FOOT	23	18			5
55101800	STORM SEWER REMOVAL 42"	FOOT	10	10			
55101900	STORM SEWER REMOVAL 48"	FOOT	30	30			
56100600	WATER MAIN 6"	FOOT	12	12			
56100900	WATER MAIN 12"	FOOT	84	84			
56400100	FIRE HYDRANTS TO BE MOVED	EACH	1	1			
56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	3	3			
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	1	1			
56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	1	1			
60107600	PIPE UNDERDRAINS 4"	FOOT	800	520			280
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2				2
60201110	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	22	17			5
60207915	CATCH BASINS, TYPE C, TYPE 11V FRAME AND GRATE	EACH	2	2			

● INDICATES SPECIALTY ITEMS

PLAN	DATE
BY	
REVIEWED	
DATE	
BY	
REVIEWED	
DATE	
BY	
REVIEWED	
DATE	
BY	
REVIEWED	
DATE	

PROFILE	DATE
BY	
REVIEWED	
DATE	
BY	
REVIEWED	
DATE	
BY	
REVIEWED	
DATE	
BY	
REVIEWED	
DATE	



REVISIONS	
NAME	DATE
M.J.L.	8-11-04

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 CHURCH ROAD
 DATE 7-9-04
 DRAWN BY SAH
 CHECKED BY M.J.L.
 SCALE: NONE

8/11/04 11:36:28 AM