



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 13, 2005

SUBJECT: FAU 2667 (Church Road)
Project M-8003(231)
Section 02-00165-00-RP (Elmhurst)
DuPage County
Contract No. 83768
Item 37
January 21, 2005 Letting
Addendum (A)

TO PROSPECTIVE BIDDERS:

To clarify information, it is necessary to add the following:

Special Provisions - Add Cleaning Existing Drainage Structures, Page SP 10.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal. Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Since the proposal sheets are displayed back to back, bidders are cautioned to exercise care when inserting revised and/or added special provisions into their proposals.

Please call 217-782-7806 if any of the above-described material is not included in this transmittal.

Very truly yours,

Michael L. Hine
Engineer of Design and Environment

A handwritten signature in black ink, reading "Ted B. Walschleger DE." The signature is written in a cursive style.

By: Ted B. Walschleger
Engineer of Project Development
and Implementation

2 inches (50 mm)	55±25
#4 (4.75 mm)	30±20
#200 (75 µm)	5±5

**The bituminous material shall be separated and mechanically blended with the crushed concrete so the bituminous material does not exceed 40% of the final product. The top size of the bituminous material in the final product shall be less than 4 inches (100 mm) and shall not contain steel slag or any other material that is considered expansive by the Department.

The Aggregate Subgrade shall be placed in two lifts consisting of a 9 inches (225 mm) and variable nominal thickness lower lift and a 3 inches (75 mm) nominal thickness top lift of capping aggregate having a gradation of CA 6. Reclaimed Asphalt Pavement (RAP) meeting Article 1004.07 of the Standard Specifications and having 100% passing the 3 inches (75 mm) sieve and well-graded down through fines may also be used as capping aggregate. RAP shall not contain steel slag or other expansive material. The results of the Department's tests on the RAP material will be the determining factor for consideration as expansive. A vibratory roller meeting the requirements of Article 1101.01 of the Standard Specifications shall be used to roll each lift of material to obtain the desired keying or interlock and necessary compaction. The Engineer will verify that adequate keying has been obtained.

When a recommended remedial treatment for unstable subgrades is included in the contract, the lower lift of Aggregate Subgrade may be placed simultaneously with the material for Porous Granular Embankment, subgrade when the total thickness to be placed is 2 feet (600 mm) or less.

Method of Measurement

- (a) Contract Quantities. Contract quantities shall be in accordance with Article 202.07.
- (b) Measured Quantities. Aggregate subgrade will be measured in place and the area computed in square yards (square meters).

Basis of Payment This work will be paid for at the contract unit price per square yard (square meter) for AGGREGATE SUBGRADE, 12" (300 mm), which price shall include the capping aggregate.

Cleaning Existing Drainage Structures

Effective: September 30, 1985

Revised: November 1, 1996

All existing storm sewers, pipe culverts, manholes, catch basins and inlets shall be considered as drainage structures insofar as the interpretation of this Special Provision is concerned. When specified for payment, the location of drainage structures to be cleaned will be shown on the plans.

Added 1-13-05