

CODE NO.	PAY ITEM	UNIT	PROJECT TOTAL	SUBTOTALS		CONSTRUCTION TYPE CODE								
				HBRP SUBTOTAL	NON PART SUBTOTAL	ARTHUR AVENUE			PRATT BOULEVARD			LUNT AVENUE		
						VILLAGE 100%	HBRP VILLAGE	80% 20%	VILLAGE 100%	HBRP VILLAGE	80% 20%	VILLAGE 100%	HBRP VILLAGE	80% 20%
						NON PART Y002 (1)	CULVERT X028-2A (1)	NON PART Y003 (2)	CULVERT X028-2A (2)	NON PART Y003 (3)	CULVERT X028-2A (3)			
• 20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	417	417	0		115		230					72
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	207	207	0		34		113					60
20101000	TEMPORARY FENCE	FOOT	1,300	1,300	0		400		450					450
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	8	8	0		3		3					2
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	7	7	0		2		5					
* 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	300	300	0		100		100					100
20700220	POROUS GRANULAR EMBANKMENT	CU YD	4,900	4,900	0		1,600		1,900					1,400
20800150	TRENCH BACKFILL	CU YD	100	100	0		30		40					30
• 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	400	400	0		100		150					150
• 21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	1,500	1,500	0		500		500					500
* 21300010	EXPLORATION TRENCH, SPECIAL	FOOT	600	600	0		200		200					200
• 25000314	SEEDING, CLASS 4B	ACRE	0.3	0.3	0.0		0.1		0.1					0.1
• 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	13	13	0		4		5					4
• 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	13	13	0		4		5					4
• 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	13	13	0		4		5					4
• 25100630	EROSION CONTROL BLANKET	SQ YD	1,500	1,500	0		500		500					500
* 25200100	SODDING	SQ YD	750	750	0		210		330					210
• 25200200	SUPPLEMENTAL WATERING	UNIT	45	45	0		13		19					13
28000400	PERIMETER EROSION BARRIER	FOOT	920	920	0		300		360					260
28100107	STONE RIPRAP, CLASS A4	SQ YD	430	430	0		150		150					130
28200100	FILTER FABRIC FOR USE WITH RIPRAP	SQ YD	630	630	0		220		220					190
31102000	SUB-BASE GRANULAR MATERIAL, TYPE C	CU YD	300	300	0		100		100					100
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	735	735	0		318		225					192
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	390	390	0		115		160					115
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	0		2							
42001300	PROTECTIVE COAT	SQ YD	408	408	0		139		119					150
* 42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2,600	2,600	0		1,000		500					1,100
* 42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	510	510	0		318							192
44000100	PAVEMENT REMOVAL	SQ YD	840	840	0		250		340					250
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	735	735	0		318		225					192
44000300	CURB REMOVAL	FOOT	60	60	0				40					20
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	804	804	0		285		387					132
44000600	SIDEWALK REMOVAL	SQ FT	1,810	1,810	0		625		472					713
44003100	MEDIAN REMOVAL	SQ FT	20	20	0		20							

• INDICATES SPECIALTY ITEM
 * INDICATES SPECIAL PROVISION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

WILLOW CREEK CULVERTS
 ARTHUR AVENUE, PRATT BOULEVARD
 AND LUNT AVENUE

NO SCALE
 DATE 11-01-04

DRAWN BY LAS
 CHECKED BY SDC