

CODE NO.	PAY ITEM	UNIT	PROJECT TOTAL	SUBTOTALS		CONSTRUCTION TYPE CODE						
				HBRP SUBTOTAL	NON PART SUBTOTAL	ARTHUR AVENUE		PRATT BOULEVARD		LUNT AVENUE		
						VILLAGE 100% NON PART Y003 (1)	HBRP VILLAGE 80% CULVERT X028-2A	VILLAGE 100% NON PART Y003 (2)	HBRP VILLAGE 80% CULVERT X028-2A	VILLAGE 100% NON PART Y003 (3)	HBRP VILLAGE 80% CULVERT X028-2A	
* 50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1	0		1					
* 50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1	0				1			
* 50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	1	0							1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	74,320	74,320	0		25,260		30,390			18,670
54003000	CONCRETE BOX CULVERTS	CU YD	576.2	576.2	0.0		197.5		234.2			144.5
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	32	32	0		32					
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	32	32	0		32					
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	64	64	0				32			32
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	16	16	0				16			
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	16	16	0				16			
* 56100900	WATER MAIN 12"	FOOT	445	445	0		240		130			75
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	0				1			
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	20	20	0		20					
* 60600605	CONCRETE CURB, TYPE B	FOOT	60	60	0				40			20
* 60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	581	581	0		285		164			132
* 60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	223	223	0				223			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8	0		2		3			3
* 67100100	MOBILIZATION	L SUM	1	1	0		0.3		0.4			0.3
* XX006119	TRAFFIC CONTROL AND PROTECTION (DETOUR)	L SUM	1	1	0		0.3		0.4			0.3
* 72000100	SIGN PANEL - TYPE 1	SQ FT	23	23	0		21.5					1.5
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	3	3	0		2					1
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	3	3	0		2		1			
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	1	1	0		1					
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	79	79	0		63					16
* X0321600	FORM LINER TEXTURED SURFACE	SQ FT	450	450	0		157		157			136
* X0632001	CLEAR PROTECTIVE COATING FOR CONCRETE	SQ FT	2,511	2,511	0		899		902			710
* X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SQ YD	850	850	0		250		350			250
* X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	26	26	0				26			
* X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	110	110	0		33		44			33
* X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	120	120	0		36		48			36
* X5121800	PERMANENT STEEL SHEET PILING	SQ FT	3,285	3,285	0		1,208		1,143			934
* XZ191300	AGGREGATE SUBGRADE	CU YD	535	535	0		165		310			60
* Z0067900	STEEL CASINGS 24"	FOOT	120	120	0		40		40			40
* Δ Z0076600	TRAINEES	HOUR	Δ 500	500	0		500					

● INDICATES SPECIALTY ITEM  
 \* INDICATES SPECIAL PROVISION  
 Δ - Y080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

WILLOW CREEK CULVERTS  
 ARTHUR AVENUE, PRATT BOULEVARD  
 AND LUNT AVENUE

NO SCALE  
 DATE 11-01-04

DRAWN BY LAS  
 CHECKED BY SDC