

FAS ROUTE NO	SEC	COUNTY	TOTAL SHEETS	SHEET NO
-	*	LEE	23	2

ILLINOIS PROJECT TE-D2(115)

\* 01-P4000-00-BT

**SUMMARY OF QUANTITIES**  
CONSTRUCTION TYPE CODE: Y047

ITEM NUMBER	ITEM	UNIT	QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	26
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	120
20200100	EARTH EXCAVATION	CU. YD.	1060
25000900	SEEDING, CLASS 1, SPECIAL	ACRE	0.26
28000400	PERIMETER EROSION BARRIER	FOOT	642
28100109	STONE RIPRAP, CLASS A5	SQ. YD.	123
28200100	FILTER FABRIC FOR USE WITH RIPRAP	SQ. YD.	123
35101400	AGGREGATE BASE COURSE, TYPE B	TON	1041
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	225
40500100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	781
40500300	BITUMINOUS MIXTURE COMPLETE	TON	200
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	1
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ. FT.	179
44000500	COMBINATION CURB & GUTTER REMOVAL	FOOT	60
44000600	SIDEWALK REMOVAL	SQ. FT.	591
50300225	CONCRETE STRUCTURES	CU. YD.	73.8
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	10450
51204900	STEEL SHEET PILING	SQ. FT.	220
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	18
60242700	INLETS, SPECIAL, NO. 3	EACH	1
60255500	MANHOLES TO BE ADJUSTED	EACH	1
60400105	FRAMES, TYPE 1	EACH	1
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	425
63200310	GUARDRAIL REMOVAL	FOOT	38
63400305	GUARD POST, SPECIAL	EACH	2
72000100	SIGN PANEL, TYPE 1	SQ. FT.	23.72
72900100	METAL POST, TYPE A	FOOT	100
78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ. FT.	2.9
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	221
78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	117
81012600	CONDUIT IN TRENCH, 2" DIA. PVC	FOOT	168
81400100	HANDHOLE	EACH	1
A2001714	TREE ACER SACCHARUM (SUGAR MAPLE), 1 3/4" CALIPER, BALLED & BURLAPPED	EACH	8
A2007114	TREE QUERCUS RUBRA (RED OAK) 1 3/4" CALLIPER, BALLED & BURLAPPED	EACH	8
B2005064	TREE MALUS SNOWDRIFT (SNOWDRIFT CRAB APPLE) 5' HEIGHT CLUMB FORM, BALLED & BURLAPPED	EACH	8
X0322973	REMOVE EXISTING SEA WALL	FOOT	81
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ. FT.	918
Z0002600	BAR SPLICERS	EACH	47
Z0069200	STONE RETAINING WALL	SQ. FT.	260
XX005803	BRICK SURFACE COURSE	SQ. YD.	429
XX005804	FORM LINER TEXTURED SURFACE	SQ. YD.	15.4
XX005805	LIGHT POLE FOUNDATION, 20" DIAMETER	EACH	3

**GENERAL NOTES**

- THE FINAL TOP 100 MM (FOUR INCHES) OF SOIL IN ANY AREA DISTURBED BY THE CONTRACTOR MUST BE A COHESIVE SOIL CAPABLE OF SUPPORTING VEGETATION.
  - WHEN MULCH WITH EMULSIFIED ASPHALT IS APPLIED, IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO COVER OR PROTECT ALL TRAFFIC SIGNS, GUARDRAILS AND CURBS. ANY SIGNS, GUARDRAIL OR CURBS WHICH BECOME COVERED WITH ASPHALTIC MATERIAL SHALL BE CLEANED BY THE CONTRACTOR AT HIS OWN EXPENSE.
  - A NATIONWIDE 404 PERMIT HAS BEEN ISSUED FOR THIS PROJECT AND THE CONDITIONS OF THAT PERMIT MUST BE ADHERED TO.
  - ALL FRAMES AND GRATES OF DRAINAGE STRUCTURES TO BE REMOVED OR FILLED SHALL BE CAREFULLY SALVAGED AND SHALL REMAIN THE PROPERTY OF THE DIXON PARK DISTRICT.
  - THE COST OF MAKING SEWER CONNECTIONS TO EXISTING DRAINAGE STRUCTURES SHALL BE INCLUDED IN THE VARIOUS CONTRACT UNIT PRICES FOR STORM SEWER.
  - THE NEW MANHOLE LIDS ON THIS PROJECT SHALL HAVE THE WORD "STORM", "SANITARY", OR "WATER" ON THE LID. THE WORD TO BE USED IS NOTED ON THE PLANS. IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE WORD TO BE USED ON OTHER LIDS NOT NOTED ON THE PLANS. NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR THIS WORK.
  - ALL PROPOSED MANHOLES AND INLETS ON THIS PROJECT SHALL BE CAST IN PLACE OR PRECAST. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR MANHOLE OR CONTRACT UNIT PRICE EACH FOR INLET SPECIAL - NO. 3 OF THE TYPE AND SIZE SPECIFIED. ONLY BICYCLE SAFE GRATES SHALL BE USED ON THIS PROJECT.
  - THE CONTRACTOR SHALL DETERMINE FLOWLINES OF EXISTING SEWER LINES WHICH ARE SHOWN ON THE PLANS AS ESTIMATED OR UNKNOWN. THIS INFORMATION IS NECESSARY BEFORE ORDERING INLETS AND MANHOLES.
  - WORK ON THIS PROJECT SHALL NOT INTERFERE WITH THE ANNUAL DIXON PETUNIA FESTIVAL HELD ALONG THE RIVERFRONT OR RECREATIONAL EVENTS PLANNED BY THE DIXON PARK DISTRICT. ALSO THE CITY OF DIXON WILL BE COMPLETING THE BIKE PATH UNDER THE PEORIA AVENUE BRIDGE IN THE YEAR 2005. WORK ON THIS PROJECT SHALL BE SCHEDULED TO KEEP INTERFERENCE BETWEEN THE RECREATION EVENTS, PROJECTS AND CIVIC EVENTS TO A MINIMUM. THE CONTRACTORS SHALL INFORM EACH OTHER, THE CITY OF DIXON, AND THE DIXON PARK DISTRICT OF PROGRESS OF THE PROJECTS AND GIVE FAIR WARNING WHEN A PROBLEM MIGHT BE ENCOUNTERED.
  - THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED FOR NON-EMERGENCY WORK. THE JULIE NUMBER IS 800-892-0123. THE FOLLOWING IS A LIST OF THE UTILITY MEMBERS AND THE STATUS OF THEIR FACILITIES LOCATED WITHIN OR ADJACENT TO THE PROJECT CONSTRUCTION LIMITS.
- | UTILITY NAME            | TYPE      | LOCATION           |
|-------------------------|-----------|--------------------|
| NICOR GAS CO.           | GAS       | THROUGHOUT PROJECT |
| COMMONWEALTH EDISON CO. | ELECTRIC  | THROUGHOUT PROJECT |
| GALLATIN RIVER          | TELEPHONE | THROUGHOUT PROJECT |
| NORLIGHT TELECOMM.      | TELEPHONE | ALONG RIVER STREET |
| INSIGHT CABLE           | CABLE     |                    |
| DIXON SANITATION DEPT.  | SEWER     | THROUGHOUT PROJECT |
| DIXON WATER DEPT.       | WATER     | THROUGHOUT PROJECT |
- THE INFORMATION ABOVE IS PROVIDED FOR THE CONVENIENCE OF THE BIDDER AND REFLECTS THE BEST INFORMATION AVAILABLE AT THE TIME OF PLAN SUBMITTAL. THIS INFORMATION IS NOT INTENDED TO INDICATE THAT THESE WILL BE THE ONLY UTILITY CONFLICTS THROUGHOUT THE PROJECT. THE APPLICABLE PROVISIONS OF ARTICLES 105.07, 107.20, 107.31 AND 108.02 OF THE STANDARD SPECIFICATIONS SHALL APPLY. CONTACT PERSONS, PHONE NUMBERS, AND ADDRESSES WILL BE SUPPLIED AFTER THE AWARD OF THE CONTRACT. ESTIMATED UTILITY RELOCATION DATES OR WORKING DAYS SHOULD BE PART OF THE PROGRESS SCHEDULE SUBMITTED BY THE CONTRACTOR. IF ANY UTILITY ADJUSTMENTS OF RELOCATIONS HAVE NOT BEEN COMPLETED PER THE ABOVE COMMENTS, THE CONTRACTOR SHOULD NOTIFY THE ENGINEER IN WRITING.
- FOR SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID, SELF-SEALING LIDS SHOULD BE USED AND THE WORD "SANITARY" IMPRINTED ON SAID COVER. COST OF THIS WORK SHALL BE INCLUDED IN THE COST OF MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID.
  - THE REMOVAL OF BITUMINOUS SURFACING REMOVED IN CONJUNCTION WITH THE BASE SHALL BE REMOVED AS EARTH EXCAVATION.
  - ALL FULL DEPTH SAW CUT PERFORMED SHALL BE INCIDENTAL TO THE CONTRACT.
  - EARTHWORK NECESSARY TO CONSTRUCT THE PCC SIDEWALK SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR PCC SIDEWALK 5".
  - THE BRICK SURFACE COURSE SHALL MATCH THE COLOR AND PATTERN THAT IS ON THE ADJACENT BRICK EMBOSSED ASPHALT PATH NEAR STATION 111+50.
  - THE LOCATION OF THE TREE REPLACEMENT PLANTINGS SHALL BE DETERMINED BY THE DIXON PARK DISTRICT AND SHALL BE PLANTED IN THE FALL.
  - AGGREGATE SURFACE COURSE, TYPE B IS PROVIDED IN THE PLAN QUANTITIES AND SHALL BE USED TO CONSTRUCT THE TEMPORARY RAMPS UNDER THE PEORIA AVENUE BRIDGE TO TRANSITION TO EXISTING SURFACE UNTIL NEW PEORIA AVENUE BRIDGE IS CONSTRUCTED.


© WENDLER ENGINEERING SERVICES, INC. 2004

**WENDLER ENGINEERING SERVICES, INC.**

Structural & Civil Engineers—Land Surveying—Environmental Services  
Illinois Professional Design Firm No. 184-000848



698 TIMBER CREEK ROAD - P.O. BOX 486 - DIXON, IL 61021 - 815-288-2261  
28 E. MARION - SUITE 3 - PRINCETON, IL 61356 - 815-879-4731  
1770 WEST STATE ST. - SYCAMORE, IL 60178 - 815-895-5008  
804 FREETPORT RD. - STERLING, IL 61081 - (815) 626-4428  
E-MAIL: info@wendler.nu



REVISION	DATE	SURVEYED BY	JOB NO.	DRAWN BY	DESIGNED BY
			99022	BDS	
		BOOK NO.	DRAWING NAME	DRAWING DATE	
			NOTES	2/3/2004	
TITLE: <b>SUMMARY OF QUANTITIES &amp; GENERAL NOTES</b>					
CLIENT: <b>DIXON PARK DISTRICT</b>					