

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
80	*	LASALLE	460	4

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT
 *150-2HBR, 171XIN&TS-1

SUMMARY OF QUANTITIES					← ACF →			← ACIM →			
CODE NO.	ITEM	UNIT	TOTAL QTY	URBAN		CONSTRUCTION TYPE CODE			90% FED 10% STATE		
				I 000-2A ROADWAY IL 351	J000-2A ROADWAY IL 351	Y 031-1F TRAFFIC SIGNALS 80% FED 10% STATE IL 351	I000-2A STATE ENTRANCE 80% FED 20% STATE IL 351	Y030-1E LIGHTING 100% CITY IL 351	I 000-2A ROADWAY I-80	J000-2A I-80	X771-2A EXIST S.N. 050-0026 PROP. SN 050-0230 I-80
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	1761							1761	
35100100	AGGREGATE BASE COURSE, TYPE A	TON	465	465							
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	3400							3400	
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	1430	1,430							
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	470		470						
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	8415	895						7520	
40600300	AGGREGATE (PRIME COAT)	TON	13	13							
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20							
40600895	CONSTRUCTING TEST STRIP	EACH	3							3	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	181	181							
40600990	TEMPORARY RAMP	SQ YD	136	136							
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	133	133							
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	11176								11176
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	7118		7118						
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	328								328
42001300	PROTECTIVE COAT	SQ YD	334								334
42100215	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4"	SQ YD	688								688
42100815	PAVEMENT REINFORCEMENT 9 3/4"	SQ YD	688								688
42101300	PROTECTIVE COAT	SQ YD	688								688
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	325	325							
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	487	487							
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	3839	3839							
44000100	PAVEMENT REMOVAL	SQ YD	25468	5148							20320
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1749	1749							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2372	1086							1286
44000710	BITUMINOUS BASE COURSE REMOVAL	SQ YD	2938	2938							
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	1346	1346							
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	4793	4793							
44003100	MEDIAN REMOVAL	SQ FT	2430								2430
44004250	PAVED SHOULDER REMOVAL	SQ YD	17150								17150
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	196.9	196.9							
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	17.6	17.6							
44300900	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	FOOT	3297	3297							
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2626	146							2480
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	5520	230						5290	
48202850	BITUMINOUS SHOULDERS SUPERPAVE 12 1/2"	SQ YD	5975							5975	
48300415	PORTLAND CEMENT CONCRETE SHOULDERS 9 3/4"	SQ YD	6460								6460

* INDICATES SPECIALTY ITEM

11/1/2004 c:\pro\lects\002994\cvrshf.dgn