

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	*	LASALLE	460	13

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

\*50-2HBR, 71XIN&TS-1

← ACF →

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN TOTAL QTY	80% FED 20% STATE		CONSTRUCTION TYPE CODE			90% FED ACIM 10% STATE		EXIST S.N. 050-0026 PROP. SN 050-0230 I-80
				I 000-2A ROADWAY IL 351	J000-2A ROADWAY IL 351	Y 031-1F TRAFFIC SIGNALS 80% FED 10% STATE 10% CITY IL 351	I000-2A STATE ENTRANCE 80% FED 20% STATE IL 351	Y030-1E LIGHTING 100% CITY IL 351	I 000-2A ROADWAY I-80	J000-2A I-80	
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	549	549							
X4073061	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 9"	SQ YD	5300						5300		
X4073201	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 16"	SQ YD	7605						7605		
X6013600	PIPE UNDERDRAINS 4" (MODIFIED)	FOOT	10055							10055	
X6050700	REMOVE INLET BOX	EACH	6							6	
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	18							18	
* X8801310	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4			4					
* X8801345	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2			2					
* X8801350	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2			2					
* X8801395	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2			2					
* X8801400	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2			2					
XX005427	STORM SEWER WATER MAIN 36"	FOOT	95	95							
Z0022800	FENCE REMOVAL	FOOT	3395	285						3110	
* Z0002600	BAR SPLICERS	EACH	947								947
□ Z0014700	CULVERT TO BE CLEANED	EACH	8							8	
○ Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	4							4	
○ Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4							4	
○ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	6							6	
○ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	6							6	
Z0047300	PROTECTIVE SHIELD	SQ YD	668.4								668.4
Z0050800	REMOVE AND RESET RAISED PAVEMENT MARKERS	EACH	140							140	
<del>X0324678</del>	ADJUSTING SANITARY SEWER SERVICE LINE	EACH	10	10							
<del>X0420500</del>	TEMPORARY PAVEMENT PATCH.	SQ YD	112.3	112.3							
<del>X0410415</del>	ELECTRICAL CONNECTION TO SIGN STRUCTURE (TRUSS TYPE)	EACH	2							2	
<del>X0324881</del>	INLETS, TYPE A, TYPE 11V FRAME AND GRATE 48" DEPTH	EACH	5							5	
<del>X0324889</del>	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	1							1	
* X2500322	SEEDING, CLASS 5A (MODIFIED)	ACRE	4.5							4.5	
<del>X0324461</del>	ERECTING FLOATING BEARINGS, GUIDED EXPANSION, 125K	EACH	16								16
<del>X0324660</del>	ERECTING FLOATING BEARINGS, FIXED - 250K	EACH	8								8

\* INDICATES SPECIALTY ITEM  
 □ NON-PARTICIPATING  
 ○ SFTY-3N

11/1/2004 c:\pro\jects\860299A\cvs\shh.dgn