

**SCHEDULE OF QUANTITIES**

**SCHEDULE OF QUANTITIES**

**CONTRACT NO. 86603**

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE		
				I000-2A	J000-2A	X271-2A
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	5		5	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1		1	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2		2	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	4		4	
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2		2	
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2		2	
54215436	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 36"	EACH	2		2	
54215991	REINFORCED CONCRETE PIPE ELBOW 36"	EACH	1		1	
54245205	INLET BOX, STANDARD 542511	EACH	2		2	
54245605	INLET BOX, STANDARD 542536	EACH	2		2	
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	4		4	
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	2		2	
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	2		2	
54248510	CONCRETE COLLAR	CU YD	4.4		4.4	
55009700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	100		100	
55009700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	400		400	
55020700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15"	FOOT	66		66	
55020700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 36"	FOOT	98		98	
55100000	STORM SEWER REMOVAL 10"	FOOT	144		144	
55100000	STORM SEWER REMOVAL 12"	FOOT	190		190	
55100000	STORM SEWER REMOVAL 15"	FOOT	53		53	
58600000	SAND BACKFILL	CU YD	668.4			668.4
58700200	BRIDGE SEAT SEALER	SO FT	266.8			266.8
60000000	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	30		30	
60009000	PIPE DRAINS 6"	FOOT	50		50	
60100925	PIPE DRAINS 8"	FOOT	50		50	
60100940	PIPE DRAINS 12"	FOOT	187		187	
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	450		450	
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1		1	
60223700	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1		1	
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1		1	
60235110	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID (48" DEPTH)	EACH	1		1	
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2		2	
60500050	REMOVING CATCH BASINS	EACH	3		3	
60500060	REMOVING INLETS	EACH	6		6	
60500805	MANHOLES TO BE FILLED TO MAINTAIN FLOW	EACH	1		1	

\* INDICATES SPECIALTY ITEM

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE		
				I000-2A	J000-2A	X271-2A
60620400	CONCRETE MEDIAN, TYPE SB-9.06	SO FT	2220		2220	
60620600	CONCRETE MEDIAN, TYPE SB-9.06 (MODIFIED)	SO FT	3450		3450	
60620700	CONCRETE MEDIAN, TYPE SB-9.06 (SPECIAL)	SO FT	1974		1974	
60900315	TYPE D INLET BOX, STANDARD 609006	EACH	2		2	
60900515	CONCRETE THRUST BLOCKS	EACH	6		6	
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	200		200	
61100600	MISCELLANEOUS CONCRETE	CU YD	10		10	
61101015	STORM SEWERS PROTECTED, CLASS A, 12"	FOOT	100		100	
61101020	STORM SEWERS PROTECTED, CLASS A, 18"	FOOT	100		100	
61103100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	10		10	
61104000	STORM SEWERS, SPECIAL 8"	FOOT	100		100	
61104000	STORM SEWERS, SPECIAL 12"	FOOT	100		100	
61104000	STORM SEWERS, SPECIAL 18"	FOOT	100		100	
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	2250		2250	
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4		4	
63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1		1	
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	5		5	
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	6		6	
63300110	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	337.5		337.5	
63500005	DELINEATORS	EACH	161		161	
63500020	DELINEATOR REMOVAL	EACH	150		150	
64200105	SHOULDER RUMBLE STRIP	FOOT	10315		10315	
64500105	WOVEN WIRE FENCE, 4'	FOOT	3570		3570	
61001000	MOBILIZATION	L SUM	0.5		0.5	
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	8		8	
70100300	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	L SUM	1		1	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	7		7	
70101605	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	4		4	
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1		1	
70101900	TRAFFIC CONTROL AND PROTECTION (DETOUR 1)	L SUM	1		1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	300		300	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4000		4000	

\* INDICATES SPECIALTY ITEM

REVISIONS NAME	

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

F.A.I. 80 AT ILLINOIS ROUTE 351

SCALE: NONE  
DATE: 09/04

DRAWN BY: JOK  
CHECKED BY: MTD