

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FA180	50-2HBR	LA SALLE	460	28
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

**CONTRACT NO. 86603**

STATION	OFFSET	ALIGNMENT	SIGN PANEL			STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	METAL POST		WOOD SIGN SUPPORT	OVERHEAD SIGN STRUCTURE - SPAN		OVERHEAD SIGN STRUCTURE WALKWAY	CONCRETE FOUNDATIONS	DRILLED SHAFT CONCRETE FOUNDATIONS	REINFORCEMENT BARS	REINFORCEMENT BARS, EPOXY COATED
			TYPE 1	TYPE 2	TYPE 3		TYPE A	TYPE B		TYPE I-A (4'-0" X 4'-6")	TYPE II-A (4'-6" X 5'-3")					
			SQ FT	SQ FT	SQ FT		FOOT	FOOT		FOOT	FOOT					
633+63	RT	I-80			195	1352							2.6		98	
643+14	RT	I-80			682.5					97		52.5		18.8		2870
660+50	RT	I-80		16				32								
661+25	LT	I-80		16				32								
674+70	LT	I-80			397.5					76		35.5		14.8		2550
48+50	RT	IL 351		20				48								
49+00	LT	IL 351	13					28								
49+50	RT	IL 351	6.2					28								
50+00	LT	IL 351		10				27								
50+50	RT	IL 351	7					28								
51+67	LT	IL 351			34	293							1.4		78	
51+67	RT	IL 351			225	1456							2.8		108	
54+95	LT	IL 351		23		293							1.4		78	
56+00	LT	IL 351	9					27								
57+60	LT	IL 351	14					27								
57+60	RT	IL 351	8.4					32								
57+60	RT	IL 351	8.4					32								
58+75	RT	IL 351		20					17							
59+25	LT	IL 351	6	16				34								
60+00	RT	IL 351	4	16				38								
263+00	CL	IL 351	5					13.5								
263+00	LT	IL 351	9					27								
263+25	RT	IL 351	5					13.5								
170+70	RT	RAMP E		20					17							
172+50	LT	RAMP E			37.5				32							
176+25	RT	RAMP E	4	16				38								
141+40	RT	RAMP F			91	759							1.4		78	
149+28	RT	RAMP F			180	1995							4.2		122	
156+66	RT	RAMP F			180	1352							2.6		98	
269+00	RT	RAMP H		20					17							
271+50	LT	RAMP H			37.5				32							
TOTALS			99	193	2060	7500	165	340	115	76	97	88	16.4	33.6	660	5420

REVISIONS	NAME

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

F.A.I. 80 AT ILLINOIS ROUTE 351

SCALE: NONE  
DATE: 09/04

DRAWN BY: RJT  
CHECKED BY: MTD