

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	(70XN & TS-1	LASALLE	460	229
STA. _____		TO STA. _____		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 86603				

DESIGN		
INT.	DATE	REASON

BITUMINOUS SURFACE REMOVAL			
LOCATION	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	BITUMINOUS SURFACE REMOVAL BUTT JOINT	BITUMINOUS SHOULDER REMOVAL
	SQ. YD.	SQ. YD.	SQ. YD.
STA. 247+00.00, RT. TO STA. 249+16.23, RT.	337		
STA. 247+00.00, LT. TO STA. 260+20.00, LT.	1907		
STA. 249+16.23, RT. TO STA. 260+20.00, RT.	1595		
STA. 262+30.70 TO STA. 52+90.57			1346
2979TH STREET STA. 10+91.83		57	
NORTH 30TH ROAD			
STA. 50+00.00 TO STA. 54+74.86		124	
TOTAL	3839	181	1346

CONCRETE HEADWALL REMOVAL SCHEDULE	
LOCATION	CONCRETE HEADWALL REMOVAL
	EACH
MAINLINE	
STA. 263+47, RT. & LT.	2
CIVIC ROAD	
STA. 51+05, RT. & LT.	2
TOTALS	4

PLOTS & CHECKS		
INT.	DATE	REASON

PIPE CULVERT REMOVAL SCHEDULE	
LOCATION	PIPE CULVERT REMOVAL
	FOOT
MAINLINE	
STA. 247+80, 31' LT	60
STA. 249+24, 30' LT	36
STA. 250+74, 29' LT	39
STA. 252+57, 29' LT	61
STA. 252+97, 29' LT	38
STA. 255+12, 29.5' LT.	143
STA. 260+47, 32' LT.	40
STA. 263+47	63
CIVIC ROAD	
STA. 44+98.55, 28.04' LT.	19
STA. 46+53.57, 28.69' LT.	71
STA. 51+04.89	40
STA. 52+39.43, 25.05' LT.	36
STA. 54+36.40	40
STA. 56+37.64, 24.30' RT.	23
TOTALS	709

SEEDING SCHEDULE						
LOCATION	SEEDING CLASS 1A	NITROGEN FERTILIZER NUTRIENT	PHOSPHOROUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING
	ACRES	POUND	POUND	POUND	ACRE	POUND
MAINLINE						
STA. 246+00, RT. TO STA. 249+16.23, RT	0.3	27	27	27	0.3	90
STA. 246+00, LT TO STA. 262+30.70, LT	1.0	90	90	90	1.0	300
STA. 249+16.23, RT TO STA. 262+30.70, RT	0.6	54	54	54	0.6	180
STA. 262+30.70, RT TO STA. 52+90.57, RT	0.6	54	54	54	0.6	180
STA. 262+30.70, LT TO STA. 52+90.57, LT	0.6	54	54	54	0.6	180
CIVIC ROAD						
STA. 43+85, LT TO STA. 50+00.00, LT	0.2	18	18	18	0.2	60
STA. 43+85, RT TO STA. 50+00.00, RT	0.2	18	18	18	0.2	60
STA. 50+00.00, LT TO STA. 54+74.86, LT	0.2	18	18	18	0.2	60
STA. 50+00.00, RT TO STA. 54+74.86, RT	0.4	36	36	36	0.4	120
TOTALS	4.1	369	369	369	4.1	1230

FILE NAME = \$FILES	BY _____
PLOT SCALE = \$DATE	DATE _____
PLOT DATE = \$DATE	
PLOT TIME = \$TIME	
OPERATOR = \$USER	
PROFILE SURVEYED _____	
NOTE BOOK _____	
REVISION _____	
STRUCTURE NOTING CHRD _____	

CHECKS		
INT.	DATE	REASON

CURB REMOVAL SCHEDULE	
LOCATION	CONCRETE CURB AND GUTTER REMOVAL
	FOOT
MAINLINE	
STA. 262+30.70 TO STA. 52+90.57	1019
CIVIC ROAD	
STA. 43+84 TO STA. 50+00	67
TOTAL	1086

MEDIAN SURFACE REMOVAL	
LOCATION	CONCRETE MEDIAN SURFACE REMOVAL
	SQ. FT.
MAINLINE	
STA. 262+30.70 TO STA. 52+90.57	4793
TOTALS	4793

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAU 6108 (IL. RTE. 351)
SECTION (70XN & TS-1)
LASALLE COUNTY

SCALE: VERT. _____
HORIZ. _____
DATE: 08/13/04

DRAWN BY: BISHOP
DESIGNED BY: KUNTZMAN
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD

COMPUTER FILE NO. SCHEDULE.B-02
PROJECT 01194.B.N
08/13/04-RPB