F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	(70X)N & TS-1	LA SALLE	460	368
STA. 41+00	TO STA. 47+00			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 86603

N

0 20 40

SCALE IN FEET

STA. 46+85, 31.20' LT.
PIPE CULVERTS, CLASS A, TYPE 1
EQUIVALENT ROUND-SIZE 24"
66 FOOT @ 0.90%
W/ (2) PRCFES EQUIVALENT ROUND-SIZE 24"
USFL = 639.26 (+26.5, 31.2' LT.)
(END OF PIPE)
DSFL = 638.67 (+92.5, 31.2' LT.)
(END OF PIPE)

STA. 44+98.55, 28.04' LT.
15" CMP
USFL = 640.42
DSFL = 640.07
19 FOOT PIPE
CULVERT REMOVAL

STA. 46+53.57, 28.69' LT.
15" RCCP
USFL = 639.22
DSFL = 638.36
71 FOOT PIPE
CULVERT REMOVAL

STA. 44+95, 28.31' LT.
PIPE CULVERTS, CLASS A, TYPE 1 15"
64 FOOT @ 0.80%
W/ (2) PRCFES 15"
USFL = 640.70 (+63, 27.6' LT.)
(END OF PIPE)
DSFL = 640.18 (+27, 29.1' LT.)
(END OF PIPE)

+01 C.E. CONC.
ASP.
CONC.
EXIST. R.O.W.
41
42
43
44
45+00
46
+34 C.E. ASP.
+68 C.E. CONC.
MATCHLINE STA. 47+00

STA. 43+84.00
BEGIN IMPROVEMENT

CONC.
EXIST. R.O.W.
WV
AGG.
+12 C.E. CONC.
+20 C.E. AGG.
+15 C.E. ASP.
+92 C.E. ASP.

STA. 45+92, 34' RT.
PIPE CULVERTS, CLASS A, TYPE 1 15"
94 FOOT @ 1.00%
W/ (2) PRCFES 15"
USFL = 640.04 (+45, 31' RT.)
(END OF PIPE)
DSFL = 639.09 (+39, 33' RT.)
(END OF PIPE)

DESIGN

INT.	DATE	REASON

PLOTS & CHECKS

INT.	DATE	NO.	REASON

FILE NAME = $FILE$
PLOT SCALE = $SCALE$
PLOT DATE = $TIME$
PLOT TIME =
OPERATOR = $USER$

CHECKS

INT.	DATE	REASON

REVISIONS

NAME	DATE
MABUS	09/15/03

ILLINOIS DEPARTMENT OF TRANSPORTATION

DRAINAGE AND UTILITIES PLAN

FAU 6108 (IL. RTE. 351)
SECTION (70X)N & TS-1
LASALLE COUNTY

SCALE: VERT.
HORIZ.
DATE: 06/30/03

DRAWN BY: MABUS
DESIGNED BY: BOTT
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC. OF SPRINGFIELD
CONSULTING ENGINEERS
SUCCESSIT LIMEN OPUS
3010 HOLIDAY DRIVE, P.O. BOX 19247
SPRINGFIELD, ILLINOIS 62794-9247
PROFESSIONAL DESIGN FIRM NO. 184-000471
PROFESSIONAL & STRUCTURAL ENGINEERING CORPORATION
(217) 793-3944, (217) 793-9237 (FAX), E-MAIL: GNGBSPRINGFIELD@AOL.COM

COMPUTER FILE NO.
SS351K-01

PROJECT: 01194_B_N
04/27/04-RPB

IDOTPL-20 1"=20' 8/07/00

CIVIC ROAD - DRAINAGE & UTILITIES - FAU RTE. 6108 (IL RTE. 351) LASALLE CO.