

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
828	12BR-2	CUMBERLAND	32	6
STA.		TO STA.		
FED. ROAD DIST. NO. 5		ILLINOIS	FED. AID PROJECT	

90920

EROSION CONTROL

LOCATION		TEMPORARY DITCH CHECK (EACH)	INLET AND PIPE PROTECTION (EACH)
STATION	SIDE		
IL ROUTE 121			
11+712.420	LT	1	
11+722.600	LT	1	
11+733.160	LT	1	
11+743.340	LT	1	
11+753.690	LT	1	
11+763.770	LT	1	
MONTROSE ROAD			
100+063.180	RT		1
100+074.550	RT	1	
TOTAL:		7	1

EROSION CONTROL BLANKET

LOCATION		EROSION CONTROL BLANKET (SQ. M)
STATION	SIDE	
MONTROSE ROAD		
100+010.000 TO 100+038.000	RT	109.1
100+010.000 TO 100+070.000	LT	426.5
100+050.000 TO 100+079.790	RT	282.7
TOTAL:		818.3

EARTHWORK FOR EROSION CONTROL

LOCATION		EARTH EXCAVATION FOR EROSION CONTROL (CU. M)	AGGREGATE (EROSION CONTROL) (M. TON)
STATION	OFFSET		
IL ROUTE 121			
11+706.268	16.031 LT	5	1
TOTAL:		5	1

RIPRAP SCHEDULE

LOCATION		STONE RIPRAP CLASS A3 (SQ. M)	STONE RIPRAP CLASS A4 (SQ. M)	FILTER FABRIC FOR USE WITH RIPRAP (SQ. M)
STATION	SIDE			
IL ROUTE 121				
11+703.623 TO 11+755.003	LT		305	305
11+755.003 TO 11+763.623	LT	16		
MONTROSE ROAD				
100+047.773 TO 100+075.810	RT		192	192
100+091.742 TO 100+097.326	RT		24	24
TOTAL:		16	521	521

PAVEMENT MARKING SCHEDULE

LOCATION		PAINT PAVEMENT MARKING LINE 100 MM (M)	SHORT-TERM PAVEMENT MARKING (M)	DESCRIPTION
STATION	LENGTH			
IL ROUTE 121				
11+701.000 TO 11+756.037	55	110	5	CL - DOUBLE YELLOW
11+701.000 TO 11+756.037	55	55		LT EDGE - SOLID WHITE
MONTROSE ROAD				
100+048.211 TO 100+072.423	24	48	2.4	CL - DOUBLE YELLOW
100+016.900 TO 100+072.423	56	56		RT EDGE - SOLID WHITE
TOTAL:		269	7.4	

SEEDING SCHEDULE

LOCATION		SEEDING CLASS 2 (HA)	NITROGEN FERTILIZER NUTRIENT (KG)	PHOSPHORUS FERTILIZER NUTRIENT (KG)	POTASSIUM FERTILIZER NUTRIENT (KG)	MULCH METHOD 2 (HA)	SEEDING CLASS 7 (HA)
STATION	SIDE						
MONTROSE ROAD							
100+000.00 TO 100+040.000	RT	0.010	1	1	1	0.010	0.010
100+010.000 TO 100+020.000	LT	0.001	0.1	0.1	0.1	0.001	0.001
100+040.000 TO 100+070.000	LT	0.002	0.2	0.2	0.2	0.002	0.002
100+045.430 TO 100+050.000	RT	0.001	0.1	0.1	0.1	0.001	0.001
100+060.000 TO 100+070.000	RT	0.006	0.6	0.6	0.6	0.006	0.006
TOTAL:		0.02	2	2	2	0.02	0.02
PAY TOTAL:		0.1	10	10	10	0.1	0.1

FURNISHING & ERECTING ROW MARKERS

LOCATION		ROW MARKERS (EACH)
STATION	OFFSET	
IL ROUTE 121		
11+700.000	12.190 LT	1
11+700.000	23.160 LT	1
11+755.000	12.190 LT	1
11+755.000	23.160 LT	1
MONTROSE ROAD		
100+035.000	16.921 RT	1
100+035.000	25.908 RT	1
100+085.000	16.824 RT	1
100+085.000	25.908 RT	1
TOTAL:		8

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF QUANTITIES  
 FAP 828 (MONTROSE RD.)  
 CUMBERLAND COUNTY  
 STATION 11+724.930  
 DATE \_\_\_\_\_  
 DRAWN BY OLDENDORPH  
 CHECKED BY STEUART

\\tr\p8\18012\tdgntech\21a.dgn 05/18/2003 06:15:51 AM