

SCHEDULE OF QUANTITIES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
601	(*)	PIKE	51	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

(*) 02-00077-00-RS

GUARDRAIL SCHEDULE											
STATION BEGIN	TO	STATION END	LT/RT	GUARDRAIL REMOVAL (FOOT)	VERTICAL ADJ. OF GUARDRAIL, TY A (FOOT)	SPBGR TYPE A (FOOT)	TRAF BAR TERM TYPE 2 (EACH)	TRAF BAR TERM TYPE 5 (EACH)	TRAF BAR TERM TY 1 SP (TAN) (EACH)	TERM MARKERS DIRECT APPLIED (EACH)	GUARDRAIL MARKERS TY A (EACH)
88+24.0		88+74.0	RT						1	1	
88+74.0		89+11.5	RT			37.50					1
89+11.5		89+36.5	RT	25.00		25.00					1
89+36.5		93+24.0	RT		387.50						10
93+24.0		93+49.0	RT	25.00							1
93+49.0		93+74.0	RT						1	1	
89+00.0		89+50.0	LT	50.00					1	1	
89+50.0		93+25.0	LT		375.00						10
93+25.0		93+50.0	LT	25.00		25.00					1
93+50.0		94+00.0	LT						1	1	
102+37.5		102+87.5	RT	12.50					1	1	
102+87.5		102+75.0	RT	25.00		25.00					1
102+75.0		106+25.0	RT		337.50						9
106+25.0		106+75.0	RT	25.00					1	1	
101+50.0		102+00.0	LT						1	1	
102+00.0		102+12.5	LT			12.50					1
102+12.5		102+37.5	LT	25.00		25.00					1
102+37.5		106+50.0	LT		412.50						11
106+50.0		107+00.0	LT	50.00					1	1	
118+12.0		118+62.0	RT						1	1	
118+62.0		120+62.0	RT			200.00					5
120+62.0		121+87.0	RT	125.00		125.00					4
121+87.0		122+37.0	RT	50.00					1	1	
130+94.3		131+44.3	RT						1	1	
131+44.3		132+06.8	RT			62.50					2
132+06.8		132+69.3	RT	62.50		62.50					2
132+69.3		132+82.5	RT	13.25				1			
132+82.5		132+43.0	LT	10.00			1				
132+43.0		132+80.5	LT	37.50		37.50					2
132+80.5		132+93.8	LT	13.25				1			
134+45.5		134+58.8	RT	13.25							1
134+58.8		134+71.3	RT	12.50		12.50					
134+71.3		134+83.8	RT	11.00			1				
134+83.8		134+71.1	LT	13.25				1			
134+71.1		135+21.1	LT	50.00		50.00					2
135+21.1		136+96.1	LT			175.00					5
136+96.1		137+46.1	LT						1	1	
202+00.0		202+50.0	RT						1	1	
202+50.0		202+75.0	RT			25.00					1
202+75.0		203+75.0	RT	100.00		100.00					3
203+75.0		204+00.0	RT			25.00					1
204+00.0		204+50.0	RT						1	1	
203+24.0		203+74.0	LT	50.00					1	1	
203+74.0		204+24.0	LT	50.00		50.00					2
204+24.0		204+74.0	LT						1	1	
207+25.0		207+50.0	LT						1	1	
207+50.0		209+00.0	LT			150.00					4
209+00.0		209+50.0	LT						1	1	
211+86.5		212+36.5	LT	25.00					1	1	
212+36.5		212+61.5	LT	25.00		25.00					1
212+61.5		213+11.5	LT	50.00					1	1	
206+25.0		206+75.0	RT						1	1	
206+75.0		208+25.0	RT			150.00					4
208+25.0		208+75.0	RT						1	1	
211+60.0		212+10.0	RT	22.00					1	1	
212+10.0		212+47.5	RT	37.50		37.50					1
212+47.5		212+97.5	RT	40.50					1	1	
231+18.0		231+68.0	RT						1	1	
231+68.0		231+93.0	RT			25.00					1
231+93.0		232+43.0	RT	50.00		50.00					2
232+43.0		232+93.0	RT	50.00					1	1	
231+57.5		232+07.5	LT	37.50					1	1	
232+07.5		232+70.0	LT	62.50		62.50					2
232+70.0		233+45.0	LT			75.00					2
233+45.0		233+95.0	LT						1	1	
TOTALS				1,274	1,512.5	1,650	2	4	28	28	94

AGGREGATE SHOULDER SCHEDULE						
STA.	TO	STA.	DISTANCE (FT)	AVERAGE SHOULDER WIDTH (FT)	SHOULDER (SQ FT)	AGG SHOULDER TYPE B (TON)
6+48.43		13+88.00	739.57	3	2,218.71	42.2
13+88.00		30+09.82	1,621.82	6	9,730.92	184.8
34+83.61		38+13.00	329.39	6	1,976.34	37.6
38+13.00		52+65.00	1,452.00	3	4,356.00	82.7
52+65.00		132+89.14	8,024.14	6	48,144.84	913.9
134+50.44		243+51.14	10,900.70	6	65,404.20	1,241.5
TOTAL USE						2,502.7
USE						2,503

PAVEMENT MARKING SCHEDULE							
STA.	TO	STA.	SHORT-TERM PAVT MRKNG (FOOT)	TEMP PAVT MARKING LINE 5" (FOOT)	WORK ZONE PAVT MRKNG REMOVAL (SQ FT)	PAINT PAVT MRK 5" WHITE (FOOT)	PAINT PAVT MRK 5" YELLOW (FOOT)
4+90.00		53+81.00	979.00	19,564.00	326.30	9,782	9,782
53+81.00		64+54.00	215.00	3,488.00	71.66	2,146	1,342
64+54.00		67+69.00	63.00	709.00	21.00	630	79
67+69.00		76+17.00	170.00	2,756.00	56.66	1,696	1,060
76+17.00		139+00.00	1,257.00	25,132.00	418.96	12,566	12,566
139+00.00		140+18.00	24.00	384.00	8.00	236	148
140+18.00		162+06.00	438.00	4,923.00	145.99	4,376	547
162+06.00		171+89.00	197.00	3,195.00	65.66	1,966	1,229
171+89.00		191+92.00	401.00	8,012.00	133.65	4,006	4,006
191+92.00		201+92.00	200.00	3,250.00	66.66	2,000	1,250
201+92.00		211+89.00	200.00	2,244.00	66.66	1,994	250
211+89.00		222+90.00	221.00	3,579.00	73.66	2,202	1,377
222+90.00		243+51.14	413.00	8,246.00	137.65	4,123	4,123
TOTALS			4,778.00	85,482.00	1,592.51	47,723	37,759
USE			4,778	85,482	1,593	47,723	37,759

RAISED REFLECTIVE PAVEMENT MARKER SCHEDULE						
STA.	TO	STA.	DISTANCE	LOCATION	SPACING	RAISED REFL PAVEMENT MARKER (EACH)
4+90.00		77+18.93	7228.9	Tangent	80'	90
77+18.93		94+70.68	1751.8	Curve	80'	22
94+70.68		98+29.37	358.7	Tangent	80'	4
98+29.37		116+55.22	1825.9	Curve	80'	23
116+55.22		172+54.36	5599.1	Tangent	80'	70
172+54.36		192+70.72	2016.4	Curve	80'	25
192+70.72		223+50.01	3079.3	Tangent	80'	38
223+50.01		241+76.13	1826.1	Curve	80'	23
241+76.13		243+51.14	175.0	Tangent	80'	2
TOTAL USE						297

ie
consultants

INTERNATIONAL ENGINEERING CONSULTANTS, INC.
6420 SOUTH SIXTH STREET
SPRINGFIELD, ILLINOIS 62797
TEL: (217) 528-8027
FAX: (217) 528-4643
IESPRINGFIELD@IE-CONSULTANTS.COM
WWW.IE-CONSULTANTS.COM

SCHEDULE OF QUANTITIES

DRAWN BY: RG	CHECKED BY: CMS	DATE: 8-23-04	PROJECT: S03012
-----------------	--------------------	------------------	--------------------