

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
774	*	EFFINGHAM	344	6A
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	
*107WRS-1, 107BY, 107BY-1 & 107B-2				
CONTRACT NO. 94827				

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE									
PAY CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000-2A		X071-2A		X080-2A	Y030-IE		Y031-IF	Y007	
				RURAL	URBAN	RURAL	URBAN	RURAL	RURAL	URBAN	URBAN	RURAL	URBAN
60100905	PIPE DRAINS 4"	FOOT	4,152									320	3,832
60100945	PIPE DRAINS 12"	FOOT	261	140	121								
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	238	102	136								
60109520	PIPE UNDERDRAINS, FABRIC LINED TRENCH 6"	FOOT	5,641	2,660	2,981								
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE I FRAME, OPEN LID	EACH	1	1									
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1		1								
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE I FRAME, CLOSED LID	EACH	1		1								
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE B GRATE	EACH	1		1								
60222805	MANHOLES, TYPE A, 5'-DIAMETER WITH MEDIAN INLET (604106)	EACH	1		1								
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE I FRAME, CLOSED LID	EACH	1		1								
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1		1								
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1		1								
60246605	MEDIAN INLET (60410)	EACH	1		1								
60260500	INLETS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	2		2								
60266600	VALVES BOXES TO BE ADJUSTED	EACH	3	3									
60266700	VALVE BOXES TO BE RECONSTRUCTED	EACH	1	1									
60500040	REMOVING MANHOLES	EACH	10	4	6								
60500060	REMOVING INLETS	EACH	9		9								
60600095	CLASS SICRETE (OUTLET)	CU YD	14.0		14.0								
60602500	CONCRETE GUTTER, TYPE A	FOOT	1,465		1,465								
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1,218	406	812								
60623200	CONCRETE MEDIAN, TYPE SM-6.24	SO FT	1,398	1,398									
60900315	TYPE D INLET BOX, STANDARD 609006	EACH	4	2	2								
60900515	CONCRETE THRUST BLOCKS	EACH	4	2	2								
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1,100	400	700								
* 63000130	STEEL PLATE BEAM GUARD RAIL, TYPE A (SPECIAL)	FOOT	119	63	56								
* 63100075	TRAFFIC BARRIER TERMINAL, TYPE 5A	EACH	4		4								
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8	4	4								
* 63100167	TRAFFIC BARRIER TERMINAL TYPE I, SPECIAL (TANGENT)	EACH	9	3	6								
63200310	GUARDRAIL REMOVAL	FOOT	716	337	379								
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	89	86	3								
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	16	13	3								
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	21	17	4								
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	21	17	4								
67100100	MOBILIZATION	L SUM	1	.83	.17								
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	.83	.17								
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	.83	.17								
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	104	86	18								
70104490	TRAFFIC CONTROL AND PROTECTION (SPECIAL), LOCATION 1	EACH	1	.83	.17								
70104495	TRAFFIC CONTROL AND PROTECTION (SPECIAL), LOCATION 2	EACH	1	.83	.17								
70104500	TRAFFIC CONTROL AND PROTECTION (SPECIAL), LOCATION 3	EACH	1	.83	.17								
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	27,096	22,924	4,172								
70300210	TEMPORARY PAVEMENT MARKING, LETTERS & SYMBOLS	SO FT	1,846	1,451	395								
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	88,914	76,170	12,744								
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	8,371	6,942	1,429								
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	4,208	4,208									
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	225	73	152								
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2,746	1,458	1,288								

@ SN 025-0078
 @ @ SN 025-0077
 @ @ @ SN 025-3309

NOTE:
 RURAL STA. 541+93.85 TO STA. 1016+00.00
 URBAN STA. 1016+00.00 TO STA. 46+80.05
 * DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SHEET 4 OF 8

DATE 8/02

DRAWN BY ASB
CHECKED BY SJK