

SUMMARY OF QUANTITIES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
1887	6B-1	WILLIAMSON	27	3
STA. 262+55	TO STA. 263+25			
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		
CONTRACT NUMBER 98655				

CONSTRUCTION TYPE CODE

RURAL - WILLIAMSON COUNTY HBRRP FUNDING 80% FEDERAL; 20% STATE X028-2A SN 100-2021
--

CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
20200100	EARTH EXCAVATION	CU YD	441
20300100	CHANNEL EXCAVATION	CU YD	114
20700220	POROUS GRANULAR EMBANKMENT	CU YD	158
25000350	SEEDING, CLASS 7	ACRE	0.3
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	54
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	40
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	40
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.6
25001010	SEEDING, CLASS 2 (MODIFIED)	ACRE	0.3
25100115	MULCH, METHOD 2	ACRE	0.6
25100630	EROSION CONTROL BLANKET	SQ YD	423
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	33
28000300	TEMPORARY DITCH CHECKS	EACH	3
28000400	PERIMETER EROSION BARRIER	FOOT	793
28100107	STONE RIPRAP, CLASS A4	SQ YD	132.0
28200100	FILTER FABRIC FOR USE WITH RIPRAP	SQ YD	132.0
42000401	PORTLAND CEMENT CONCRETE PAVEMENT - 9" (JOINTED)	SQ YD	203
42001300	PROTECTIVE COAT	SQ YD	203
44000100	PAVEMENT REMOVAL	SQ YD	159
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	263
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	17,220
50901001	STEEL BRIDGE RAIL	FOOT	53
51500100	NAME PLATES	EACH	1
54003000	CONCRETE BOX CULVERTS	CU YD	117.2
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	225
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	370
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	3
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	LUMP SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION STANDARD 701201	LUMP SUM	1

CONSTRUCTION TYPE CODE

RURAL - WILLIAMSON COUNTY HBRRP FUNDING 80% FEDERAL; 20% STATE X028-2A SN 100-2021
--

CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	LUMP SUM	1
70300220	TEMPORARY PAVEMENT MARKING - 4"	FOOT	160
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	53
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	160
* 78200405	GUARDRAIL MARKERS	EACH	12
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
* 63300125	STEEL PLATE BEAM GUARDRAIL, (SHORT RADIUS)	FOOT	87.5
X7015050	PORTABLE CHANGEABLE MESSAGE SIGN	CAL MO	4

* SPECIALTY ITEMS

Revised: November 10, 2004 8:10:04 AM
c:\p\projects\98655\98655.dwg LJV2-63