

CONSTRUCTION TYPE CODE

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QTY.	80% FED.	80% FED.	IL. RTE. 22 & TELEGRAPH RD.	IL. RTE. 22 & WAUKEGAN RD.	IL. RTE. 22 & RIDGE RD./ TENNYSON LN.	IL. RTE. 22 & RIDGE RD.	80% FED.	50% STATE	100% HIGHLAND PARK	100% BANNOCKBURN
				20% STATE ROADWAY J000-2A	20% STATE ROADWAY I000-2A	80% FED./10% STATE 10% BANNOCKBURN TRAFFIC SIGNALS Y031-1F	80% FED. 20% STATE TRAFFIC SIGNALS Y031-1F	80% FED./10% STATE 10% HIGHLAND PARK TRAFFIC SIGNALS Y031-1F	80% FED./13.3% STATE 6.7% HIGHLAND PARK TRAFFIC SIGNALS Y031-1F	20% STATE INTERCONNECT Y031-1F	50% STATE BANNOCKBURN SIDEWALK SFTY-1B	J000-2A	J000-2A
89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	EACH	4									4	
89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	2									2	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	4			1	1	1	1				
89502380	REMOVE EXISTING HANDHOLE	EACH	37			8	15	8	6				
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	33			9	9	9	6				
A2000320	TREE, ACER MIYABEI MORTON (STATE STREET MIYABE MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	10									10	
A2004720	TREE, GLEDITSIA TRIACANTHOS INERMIS SHADEMASTER (SHADEMASTER THORNLESS COMMON HONEYLOCUST), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5									5	
A2004824	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 3" CALIPER, BALLED AND BURLAPPED	EACH	52										52
A2005016	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2" CALIPER, BALLED AND BURLAPPED	EACH	19										19
A2005620	TREE, OSTRYA VIRGINIANA (AMERICAN HOPHORNBEAM), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	6									6	
A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	22										22
A2007924	TREE, TILIA AMERICANA REDMOND (REDMOND AMERICAN LINDEN), 3" CALIPER, BALLED AND BURLAPPED	EACH	22										22
B2001916	TREE, CRATAEGUS PHAENOPYRUM (WASHINGTON HAWTHORN), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	4										4
B2005516	TREE, PYRUS CALLERYANA ARISTOCRAT (ARISTOCRAT CALLERY PEAR), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	20										20
B2006220	TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	12									12	
B2006320	TREE, SYRINGA RETICULATA IVORY SILK (IVORY SILK JAPANESE TREE LILAC), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	24									24	
C2007218	SHRUB, ROSA KNOCKOUT (KNOCKOUT ROSE), 18" HEIGHT, CONTAINER	EACH	442									442	
C2005818	SHRUB, RHUS AROMATICA GRO-LOW (GRO-LOW FRAGRANT SUMAC), 18" WIDTH, CONTAINER	EACH	510									510	
K0012990	PERENNIAL PLANTS, GALLON POT ORNAMENTAL TYPE	UNIT	23.14									23.14	
K0012990	PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT	UNIT	52.25									52.25	
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	313										313
Z0056612	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	431										431
Z0056616	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	100	100									
Z0056614	STORM SEWER (WATER MAIN REQUIREMENTS) 21 INCH	FOOT	895										895
Z0056620	STORM SEWER (WATER MAIN REQUIREMENTS) 30 INCH	FOOT	90										90
Z0056622	STORM SEWER (WATER MAIN REQUIREMENTS) 36 INCH	FOOT	30										30
Z0056626	STORM SEWER (WATER MAIN REQUIREMENTS) 48 INCH	FOOT	405										405
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	488	488									
Z0033090	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	16,334							16,334			

* SPECIALTY ITEMS □ 100% PARTICIPATION - VILLAGE OF HIGHLAND PARK Y031-3D

Rev. B-31-10 - Rev. (SHEET 8 OF 10)

FILE NAME: W:\ILRT_22\... REVISIONS\CADD Sheets	USER NAME: 160860-shi	DESIGNED: LP	REVISED:	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL. ROUTE 22 SUMMARY OF QUANTITIES		F.A.P. RTE. 337	SECTION 20R-4	COUNTY LAKE	TOTAL SHEETS 232	SHEET NO. 10	CONTRACT NO. 60860	
PLOT SCALE: \$SCA	PLOT DATE: 5/15/2010	DRAWN: LP	REVISED:		SCALE: NTS	SHEET NO. 10 OF 232 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT					
CHECKED: JP	DATE: 05/14/2010	REVISOR:	REVISOR:										