PROPOSED ROADWAY PAVEMENT							
LOCATION STATION-STATION	POLYMERIZED HOT MIX ASPHALT SURFACE 1 3/4" MIX F N90 (TON)	POLYMERIZED LEVELING BINDER (MACHINE) IL-4.75, N50 3/4" (TON)	BIT. MATERIALS (PRIME COAT) (TON)	AGGREGATE (PRIME COAT) (TON)	PORTLAND CEMENT CONCRETE PAVEMENT, 6" (SQ. YD)	AGGREGATE SUBGRADE, 12" (SQ. YD)	PORTLAND CEMENT CONCRETE PAVT. JOINTED, 10" (SQ. YD)
IL. ROUTE 22							
45+50.89 - 52+00						5954.46	5315.87
52+00 - 67+00						13091.31	5450.79
67+00 - 82+00						13723.49	10088.26
82+00 - 97+00						14589.29	10511.13
97+00 - 112+00						20393.45	18749.67
112+00 - 127+00						2539.18	2368.42
127+00 - 142+00	179.81	77.06					
142+00 - 157+00	1038.36	445.01					
157+00 - 172+00	911.40	390.60					
172+00 - 174+82.92	117.04	50.16					
LAKEWOOD DR.			0.083	0.42			
DRIVEWAY 62+97.30			0.001	0.05			
BROADLEYS CT.			0.089	0.45			
WILDWOOD DR.			0.083	0.42			
DUNSINANE LN.			0.097	0.48			
IL. ROUTE 43							
315+61.61 - 326+00	230.94	65.79				3603.24	1536.61
330+00 - 337+52.22	81.05	32.62				4804.79	3342.84
TOTAL	2558.60	1061.24	0.360	1.82		78699.21	57363.60

TEMPORARY PAVEMENT	
STAGE	QUANTITY (SQ. YD)
IL. ROUTE 43	
STAGE 1	1419.47
STAGE 2	- -
STAGE 3	- -
STAGE 4	- -
IL. ROUTE 22	
STAGE 1	13255.6
STAGE 2	1736.32
STAGE 3	- -
STAGE 4	- -
TOTAL	16411.43

PAVEMENT REPLACEMENT	
STAGE	QUANTITY (SQ. YD)
IL. ROUTE 43	
STAGE 1	- -
STAGE 2	204.74
STAGE 3	- -
STAGE 4	- -
IL. ROUTE 22	
STAGE 1	- -
STAGE 2	1348.04
STAGE 3	109.19
STAGE 4	- -
TOTAL	1661.98

HOT MIX ASPHALT SURFACE REMOVAL - BUTT JOINT		
LOCATION STA. - STA.	OFFSET	QUANTITY (SQ. YD)
IL. ROUTE 22		
RIDGE ROAD-NORTH	LT	63.04
TENNYSON LANE	RT	75.49
BENTLEY ROAD	LT	78.70
RIDGE ROAD-SOUTH	RT	71.64
MAVOR LANE	LT	83.48
ARCH. POINT LANE	LT	97.76
173+76.40-174+26.40	LT	130.86
173+74.98-174+24.98	RT	133.34
IL. ROUTE 43		
334+05.91-334+55.71	LT	147.39
337+02.23-337+52.22	RT	141.61
315+61.61-316+11.62	RT	144.27
TOTAL		1167.58

STORM SEWER REMOVAL								
LOCATION STATION-STATION	6" (FT)	8" (FT)	10" (FT)	12" (FT)	15" (FT)	18" (FT)	24" (FT)	60"x38" (FT)
IL. ROUTE 22								
45+50.89 - 52+00			77.5	541.3			73.3	
52+00 - 67+00			4.0	258.0		53.4	262.7	
67+00 - 82+00	26.5		122.3	575.7	713.8		541.9	
82+00 - 97+00				95.2				
97+00 - 112+00		33.2	104.3	188.5			228.4	454.7
112+00 - 127+00								
127+00 - 142+00				151.3	73.1			
142+00 - 157+00				686.3				
157+00 - 172+00				583.8		72.6		
172+00 - 174+82.92				62.1				
IL. ROUTE 43								
315+61.61 - 326+00				10.1			59.0	
330+00 - 337+52.22					50.3		21.4	
TOTAL	26.5	33.2	308.1	73.1	837.2	126.0	1186.7	454.7

CURB & GUTTER REMOVAL	
LOCATION STA. - STA.	QUANTITY (FOOT)
IL. ROUTE 43	
315+61.61 - 326+00	1182.90
330+00 - 337+52.22	1293.71
IL. ROUTE 22	
45+50.89 - 52+00	1405.90
52+00 - 67+00	3126.98
67+00 - 82+00	2771.06
82+00 - 97+00	2908.81
97+00 - 112+00	3692.55
112+00 - 127+00	567.28
127+00 - 142+00	581.26
142+00 - 157+00	3228.58
157+00 - 172+00	3052.53
172+00 - 174+82.92	451.79
TOTAL	24263.35

ISLAND REMOVAL			
NO.	LOCATION STA. - STA.	OFFSET	QUANTITY (SQ. FT)
IL. ROUTE 22			
1	99+29.00 - 99+61.42	LT	487.00
2	100+55.34 - 100+84.93	RT	485.53
TOTAL			972.53

FENCE REMOVAL			
NO.	LOCATION STA. - STA.	OFFSET	QUANTITY (FOOT)
IL. ROUTE 43			
1	330+00-330+63.39	RT	66.44
IL. ROUTE 22			
2	63+29.16 - 67+00.00	LT	396.65
3	67+00.00 - 67+55.83	LT	82.46
4	67+85.41 - 72+05.76	LT	475.63
5	86+66.32 - 89+78.22	RT	327.16
6	100+11.27 - 101+45.15	LT	208.13
7	104+12.26 - 105+37.66	LT	214.68
8	143+56.73 - 143+79.57	RT	30.02
TOTAL			1801.17

SIDEWALK REMOVAL			
NO.	LOCATION STA. - STA.	OFFSET	QUANTITY (SQ. FT)
IL. ROUTE 22			
1	142+80.64 - 142+97.78	LT	111.15
2	142+44.16 - 142+92.00	RT	281.96
3	143+44.48 - 144+56.71	RT	572.32
4	149+72.02 - 151+86.44	LT	1085.36
5	DRIVEWAY 150+97.08	RT	74.69
6	152+14.05 - 159+43.39	LT	3716.48
7	155+59.37 - 156+00	RT	189.27
8	155+87.81 - 156+05.49	RT	201.41
9	156+49.29 - 157+68.62	RT	653.76
10	159+64.56 - 164+99.06	LT	2632.77
11	165+44.59 - 171+72.79	LT	3227.07
12	DRIVEWAY 169+73.15	RT	268.53
TOTAL			13014.77

PAVEMENT REMOVAL	
LOCATION STA. - STA.	QUANTITY (SQ. YD)
IL. ROUTE 43	
324+35 - 326+00	515.40
324+35 - 326+00	586.01
330+00 - 334+55	1402.01
330+00 - 334+55	1215.68
IL. ROUTE 22	
45+50 - 52+00	4121.80
52+00 - 67+00	5936.56
67+00 - 82+00	5864.08
82+00 - 97+00	8295.44
97+00 - 112+00	13921.1
112+00 - 115+12	2362.83
TOTAL	44220.9

NOTE: BASIS OF MEASUREMENT AND PAYMENT PER STANDARD SPECIFICATIONS, SUPPLEMENTAL SPECIFICATIONS, AND RECURRING SPECIAL PROVISIONS UNLESS MARKED IN THE MARGIN WITH "SPL" WHICH IDENTIFIES THOSE ITEMS WHICH ARE RULED BY SECTIONS OF THE CONTRACT SPECIAL PROVISIONS.

EARTHWORK QUANTITIES																				
LOCATION	EARTH EX. (CU YD)				ADJ. EARTH EX. (15%)				EMBANKMENT (CU YD)				BALANCE WASTE (+) OR SHORTAGE (-)				UNSUITABLE (CU YD)			
	STAGE 1	STAGE 2	STAGE 3	STAGE 4	STAGE 1	STAGE 2	STAGE 3	STAGE 4	STAGE 1	STAGE 2	STAGE 3	STAGE 4	STAGE 1	STAGE 2	STAGE 3	STAGE 4	STAGE 1	STAGE 2	STAGE 3	STAGE 4
IL ROUTE 22	1,417	12,245	12,686	4,145	1,204	10,408	10,783	3,523	3,976	8,554	10,584	609	-2,772	1,854	199	2,914	4,327	8,644	6,329	0
WAUKEGAN RD	185	1,817	877	526	158	1,544	745	447	0	1,615	456	109	158	-71	289	338	0	1,730	758	1
TOTAL	1,602	14,062	13,563	4,671	1,362	11,952	11,528	3,970	3,976	10,169	11,040	718	-2,614	1,783	488	3,252	4,327	10,374	7,087	1