

SUMMARY OF QUANTITIES

URBAN
90% FED.
10% STATE

PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	0021 SAFETY
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	35	35
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,536	1,536
25000210	SEEDING, CLASS 2A	ACRE	0.32	0.32
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	29	29
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	29	29
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	29	29
25100630	EROSION CONTROL BLANKET	SQ YD	1,536	1,536
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	2,734	2,734
50102400	CONCRETE REMOVAL	CU YD	4	4
50104000	BRIDGE RAIL REMOVAL	FOOT	56	56
50300255	CONCRETE SUPERSTRUCTURE	CU YD	10	10
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5,950	5,950
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A 6 FOOT POSTS	FOOT	288	288
63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	163	163
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8	8
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	48	48
63200310	GUARDRAIL REMOVAL	FOOT	2,941	2,941
63301000	REMOVE AND REERECT STEEL PLATE BEAM GUARD RAIL	FOOT	88	88
63301990	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 1	EACH	3	3
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
78200420	GUARDRAIL MARKERS, TYPE B	EACH	123	123
78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	48	48
X0322194	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ FT	9	9
Δ X2503100	MOWING	UNIT	138	138
Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	3	3
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	154	154

* DENOTES SPECIALTY ITEM

Δ NON-PARTICIPATING

FILE NAME *	USER NAME * .USER_	DESIGNED - EF	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GUARDRAIL IMPROVEMENTS - McHENRY COUNTY SUMMARY OF QUANTITIES		F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FILEL		DRAWN - EF	REVISED -				*	2010-004-GRR	McHENRY	16	3
	PLOT SCALE * 50' / IN.	CHECKED - RS	REVISED -		SCALE: 50	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	CONTRACT NO. 60K22		
	PLOT DATE * 10/26/2010	DATE - 10/25/10	REVISED -		ILLINOIS FED. AID PROJECT						