



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 7, 2011

SUBJECT: FAP Route 338  
Section 107-RS-3  
Lake County  
Contract No. 60M58  
Item No. 110, January 21, 2011 Letting  
Addendum B

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Table of Contents to the Special Provisions
2. Revised pages 9 & 14 of the Special Provisions.
3. Deleted pages 10 - 13 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.  
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; Estimates

TBW:MS:jc

## TABLE OF CONTENTS

LOCATION OF IMPROVEMENT .....	1
DESCRIPTION OF IMPROVEMENT.....	1
MAINTENANCE OF ROADWAYS.....	1
STATUS OF UTILITIES TO BE ADJUSTED .....	2
FRAMES AND LIDS TO BE ADJUSTED (SPECIAL).....	2
TRAFFIC CONTROL PLAN.....	2
COARSE AGGREGATE FOR HOT-MIX ASPHALT (HMA) (D-1).....	3
HOT MIX ASPHALT MIXTURES, EGA MODIFIED PERFORMANCE GRADED (PG) ASPHALT BINDER5	
FINE AGGREGATE FOR HOT- MIX ASPHALT (HMA) (D-1).....	6
HOT MIX ASPHALT MIXTURE IL-4.75 (DIST 1).....	7
TEMPERATURE CONTROL FOR CONCRETE PLACEMENT (DISTRICT ONE) .....	9
USE OF RAP (DIST 1).....	14
USE OF RAS (D-1) .....	19
GRADING AND SHAPING SHOULDERS.....	23
TRAFFIC CONTROL FOR WORK ZONE AREAS .....	23
ALKALI-SILICA REACTION FOR CAST-IN-PLACE CONCRETE (BDE) .....	24
APPROVAL OF PROPOSED BORROW AREAS, USE AREAS, AND/OR WASTE AREAS (BDE) .....	27
CEMENT (BDE) .....	27
CONCRETE ADMIXTURES (BDE) .....	29
CONCRETE MIX DESIGNS (BDE) .....	32
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE).....	34
CONSTRUCTION AIR QUALITY - DIESEL VEHICLE EMISSIONS CONTROL (BDE) .....	35
CONSTRUCTION AIR QUALITY - IDLING RESTRICTIONS (BDE).....	36
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) .....	38
ENGINEER’S FIELD OFFICE TYPE A (BDE).....	45
EQUIPMENT RENTAL RATES (BDE).....	47
FRICTION AGGREGATE (BDE) .....	48
HOT-MIX ASPHALT – ANTI-STRIPPING ADDITIVE (BDE).....	50
HOT-MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS (BDE) .....	51
HOT-MIX ASPHALT – DROP-OFFS (BDE) .....	52
LIQUIDATED DAMAGES (BDE).....	52
NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM / EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE) .....	52
PAVEMENT PATCHING (BDE).....	53

Revised 01/07/2011

PAYMENTS TO SUBCONTRACTORS (BDE) ..... 53  
POST MOUNTING OF SIGNS (BDE)..... 54  
RAISED REFLECTIVE PAVEMENT MARKERS (BDE)..... 55  
SELECTION OF LABOR (BDE)..... 55  
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) ..... 55  
TEMPORARY EROSION CONTROL (BDE) ..... 56  
TRUCK MOUNTED/TRAILER MOUNTED ATTENUATORS (BDE) ..... 59  
WORKING DAYS (BDE) ..... 59  
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID)..... 60  
FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) ..... 63  
HOT MIX ASPHALT - PAY FOR PERFORMANCE USING PERCENT WITHIN LIMITS - PLANT  
SAMPLING (BMPR)..... 67

Revised 01/07/2011

“The compaction operation shall start immediately after the mixture has been placed. The Contractor shall provide a minimum of two steel-wheeled tandem rollers for breakdown ( $T_B$ ) and one finish steel-wheeled roller ( $T_F$ ) meeting the requirements of Article 1101.01(e), except the minimum compression for all of the rollers shall be 280 lb/in. (49 N/mm) of roller width. Pneumatic-tired and vibratory rollers will not be permitted.”

**TEMPERATURE CONTROL FOR CONCRETE PLACEMENT (DISTRICT ONE)**

Effective: May 1, 2007

Delete the second and third sentences of the second paragraph of Article 1020.14(a) of the Standard Specifications.

Revised 01/07/2011

This page intentionally left blank.

Deleted 01/07/2011

This page intentionally left blank.

Deleted 01/07/2011

This page intentionally left blank.

Deleted 01/07/2011

This page intentionally left blank.

Deleted 01/07/2011



**USE OF RAP (DIST 1)**

Effective: January 1, 2007

Revised: September 15, 2010

In Article 1030.02(g) of the Standard Specifications, delete the last sentence of the first paragraph in (Note 2).

Revise Section 1031 of the Standard Specifications to read:

**“SECTION 1031. RECLAIMED ASPHALT PAVEMENT**

**1031.01 Description.** Reclaimed Asphalt Pavement (RAP) results from the cold milling or crushing of an existing Hot-Mix Asphalt (HMA) pavement. The Contractor shall supply written documentation that the RAP originated from routes or airfields under federal, state, or local agency jurisdiction. The contractor can also request that a processed pile be tested by the Department to determine the aggregate quality as described in Article 1031.04, herein.

**1031.02 Stockpiles.** The Contractor shall construct individual, sealed RAP stockpiles meeting one of the following definitions. No additional RAP shall be added to the pile after the pile has been sealed. Stockpiles shall be sufficiently separated to prevent intermingling at the base. Stockpiles shall be identified by signs indicating the type and size as listed below (i.e. “Homogenous Surface”).

Prior to milling or removal of an HMA pavement, the Contractor may request the District to provide verification of the existing mix composition to clarify appropriate stockpile.

- (a) Homogeneous. Homogeneous RAP stockpiles shall consist of RAP from Class I, Superpave (High ESAL), HMA (High ESAL), or equivalent mixtures and represent: 1) the same aggregate quality, but shall be at least C quality; 2) the same type of crushed aggregate (either crushed natural aggregate, ACBF slag, or steel slag); 3) similar gradation; and 4) similar asphalt binder content. If approved by the Engineer, combined single pass surface/binder millings may be considered “homogenous” with a quality rating dictated by the lowest coarse aggregate quality present in the mixture.
- (b) Conglomerate 5/8. Conglomerate 5/8 RAP stockpiles shall consist of RAP from Class I, Superpave (High ESAL), HMA (High ESAL), or equivalent mixtures. The coarse aggregate in this RAP shall be crushed aggregate and may represent more than one aggregate type and/or quality but shall be at least C quality. This RAP may have an inconsistent gradation and/or asphalt binder content prior to processing. All conglomerate 5/8 RAP shall be processed prior to testing by crushing to where all RAP shall pass the 5/8 in. (16 mm) or smaller screen.

Revised 01/07/2011