

90% FED.  
10% STATE  
URBAN

CODE NO.	ITEM	UNIT	TOTAL	ROADWAY 0003	STRUCTURAL 0013	LANDSCAPING 0031
44213204	TIE BARS 3/4"	EACH	220	220		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,028	1,028		
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	488	488		
48300705	PORTLAND CEMENT CONCRETE SHOULDERS 12 1/4"	SQ YD	48,542	48,542		
50102400	CONCRETE REMOVAL	CU YD	214.4		214.4	
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1		
50157300	PROTECTIVE SHIELD	SQ YD	197		197	
50300100	FLOOR DRAINS	EACH	12		12	
50300225	CONCRETE STRUCTURES	CU YD	56.2	15	41.2	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	426.8		426.8	
50300300	PROTECTIVE COAT	SQ YD	551		551	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
50500505	STUD SHEAR CONNECTORS	EACH	2,748		2,748	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	118,450	900	117,550	
50800515	BAR SPLICERS	EACH	156		156	

\* DENOTES SPECIALTY ITEM

90% FED.  
10% STATE  
URBAN

CODE NO.	ITEM	UNIT	TOTAL	ROADWAY 0003	STRUCTURAL 0013	LANDSCAPING 0031
51500100	NAME PLATES	EACH	2		2	
52000110	PERFORMED JOINT STRIP SEAL	FOOT	364		364	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	8		8	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	4		4	
52100520	ANCHOR BOLTS, 1"	EACH	24		24	
52100530	ANCHOR BOLTS, 1 1/4"	EACH	8		8	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1		
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1		
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2		
54215442	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 42"	EACH	3	3		
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1		
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1	1		
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	2	2		
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	733	733		
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	945	945		

D:\proj\3384\3 east\design\sumsheet\3384-50022.dgn



USER NAME = jkjoelma	DESIGNED - CRC	REVISED -
PLLOT SCALE = 1/8" = 1' IN.	DRAWN - JMK	REVISED -
PLLOT DATE = 10/28/2010	CHECKED - MRJ	REVISED -
	DATE = 10/27/2010	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

F.A.I. 80 FROM NS RAILROAD TO US 45  
SUMMARY OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

Rev. 01-05-2011

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	99(5&S-1) Y-1	WILL	309	5
CONTRACT NO. 60M59			ILLINOIS FED. AID PROJECT	