

90% FED.  
10% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 0003	STRUCTURAL 0013	LANDSCAPING 0031
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	2,285	2,285		
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	750	750		
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	3,251	3,251		
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	3,333	3,333		
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	3,484	3,484		
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	1,105	1,105		
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	1,280	1,280		
55200900	STORM SEWERS JACKED IN PLACE, 24"	FOOT	91	91		
55201100	STORM SEWERS JACKED IN PLACE, 30"	FOOT	83	83		
55201300	STORM SEWERS JACKED IN PLACE, 36"	FOOT	270	270		
55201500	STORM SEWERS JACKED IN PLACE, 42"	FOOT	307	307		
58600100	SAND BACKFILL	CU YD	35	35		
58700300	CONCRETE SEALER	SQ FT	2,815		2,815	
59000200	EPOXY CRACK INJECTION	FOOT	120		120	
60107700	PIPE UNDERDRAINS 6"	FOOT	36,410	36,410		

\* DENOTES SPECIALTY ITEM

90% FED.  
10% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 0003	STRUCTURAL 0013	LANDSCAPING 0031
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	528	528		
60201310	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	90	90		
60201320	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 21 FRAME AND GRATE	EACH	6	6		
60219510	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	19	19		
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	9	9		
60222210	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	67	67		
60224035	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	15	15		
60500050	REMOVING CATCH BASINS	EACH	7	7		
60500060	REMOVING INLETS	EACH	4	4		
60618320	CONCRETE MEDIAN SURFACE, 6 INCH	SQ FT	325	325		
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	1,138	1,138		
* X6300130	STEEL PLATE BEAM GUARD RAIL, TYPE A (SPECIAL)	FOOT	38	38		
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	2	2		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4		
* X6310176	TRAFFIC BARRIER TERMINAL, TYPE 2 (SPECIAL)	EACH	1	1		
63200310	GUARDRAIL REMOVAL	FOOT	1,300	1,300		

Rev. 01-05-2011

	USER NAME = jkellman	DESIGNED - CRC	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>F.A.I. 80 FROM NS RAILROAD TO US 45 SUMMARY OF QUANTITIES</b>	F.A.I. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1/8" = 1' IN. PLOT DATE = 10/28/2010	DRAWN - JMK CHECKED - MRJ DATE = 10/27/2010	REVISED - REVISED - REVISED -			80 99(5&5-1) Y-1	WILL ILLINOIS	309 6	6 6

c:\pco\338613\_east\dmr\p\massheets\338613-50203.dwg