

CODE NO.	ITEM	UNIT	TOTAL	CHERRY HILL ROAD	WOLF ROAD	LAGRANGE ROAD
* 20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	30	10	10	10
* 20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	30	10	10	10
* 20100110	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	30	10	10	10
* 20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	30	10	10	10
2101605	TOPSOIL FURNISH AND PLACE, 2"	SQ YD	1600	650	300	650
2500020	SEEDING, CLASS 2A	ACRE	0.36	0.13	0.10	0.13
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	97	35	27	35
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	97	35	27	35
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	97	35	27	35
25100105	MULCH, METHOD 1	ACRE	0.36	0.13	0.10	0.13
25100630	EROSION CONTROL BLANKET	SQ YD	1600	650	300	650
44001980	CONCRETE BARRIER REMOVAL	FOOT	47	0	0	47
44001250	PAVED SHOULDER REMOVAL	SQ YD	11	0	0	11
48300705	PORTLAND CEMENT CONCRETE SHOULDERS 12 1/4"	SQ YD	5	0	0	5
50300225	CONCRETE STRUCTURES	CU YD	15	15	0	0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	900	900	0	0
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	275	275	0	0
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE T1 SPECIAL, TANGENT	EACH	1	1	0	0
* 63100175	TRAFFIC BARRIER TERMINAL, TYPE 2 (SPECIAL)	EACH	1	1	0	0
63700275	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	35	0	0	35
63700900	CONCRETE BARRIER BASE	FOOT	35	0	0	35
70101805	TRAFFIC CONTROL AND PROTECTION, (SPECIAL), STANDARD 701101	EACH	3	1	1	1
70104205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401, LOCATION 1	EACH	2	2	0	0
70104210	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401, LOCATION 2	EACH	2	0	2	0
70104215	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401, LOCATION 2	EACH	2	0	0	2
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	18	6	6	6
70400100	TEMPORARY CONCRETE BARRIER	FOOT	975	325	325	325
73300300	OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5'-0" X 7'-0")	FOOT	290	90	100	100

* DENOTES SPECIALTY ITEM ** SEE DETAILS IN PLANS

CODE NO.	ITEM	UNIT	TOTAL	CHERRY HILL ROAD	WOLF ROAD	LAGRANGE ROAD
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	126	38	44	44
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	77.8	22.0	27.9	27.9
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	54	54	0	0
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	123	41	41	41
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	3	1	1	1
* 81000500	CONDUIT IN TRENCH, 1 1/2" DIA., GALVANIZED STEEL	FOOT	90	30	30	30
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	765	0	150	615
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	150	50	50	50
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	1235	1235	0	0
* 81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	1205	1205	0	0
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	40	0	0	40
* 81400200	HEAVY-DUTY HANDHOLE	EACH	9	6	1	2
* 81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	1200	0	200	1000
* 81702415	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 6	FOOT	535	165	170	200
* 81702460	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 3/0	FOOT	1250	1250	0	0
* 81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	250	0	0	250
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	4150	2500	650	1000
* 87301715	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 18 6 PAIR	FOOT	150	150	0	0
* X0323314	FIBER OPTIC CABLE SPLICE - LATERAL	EACH	2	0	1	1
* X0324335	DMS FRONT ACCESS, FULL MATRIX, NTCIP 1203 V2 - COLOR	EACH	3	1	1	1
* X0325040	FIBER OPTIC INNERDUCT 1 1/4" DIA.	FOOT	1350	0	350	1000
* X0325815	REMOVE EXISTING CABLE	FOOT	250	0	0	250
X701015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.33	0.33	0.33
* X8710036	FIBER OPTIC CABLE 12 F SM	FOOT	1350	0	350	1000
Z003798	CONSTRUCTION LAYOUT	L SUM	1	0.33	0.33	0.33
* Z0080130	IMPACT ATTENUATORS (PARTIALLY REDIRECTIVE), TEST LEVEL 3	EACH	2	2	0	0
* Z0083023	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6	0	0	6
* N/A	DYNAMIC MESSAGE SIGN POWER CABINET, COMPLETE IN PLACE **	EACH	3	1	1	1

THESE QUANTITIES ARE IN ADDITION TO BASE CONTRACT QUANTITIES AND APPLY TO THE INSTALLATION OF THE DYNAMIC MESSAGE SIGNS

Added Sheet 1-3-11

N:\1000\1010122_000003_Mech\010122_03_00_500.dwg

CHRISTOPHER B. BURKE ENGINEERING, LTD. 9575 W. Higgins Road, Suite 600 Rosemont, Illinois 60018 (647) 823-0500	USER NAME = KBALDWIN	DESIGNED - GAH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	F.A.I. 80 FOR NS RAILROAD TO US 45 DMS BILL OF MATERIALS	F.A.I. RTE. 80	SECTION 99 (5&5-1) Y-1	COUNTY WILL	TOTAL SHEETS 188A	SHEET NO. 188A
	PLOT SCALE = 1"	CHECKED - JPC	REVISED -			SCALE: N.T.S.	SHEET NO. OF SHEETS STA. TO STA.	CONTRACT NO. 60M59		ILLINOIS FED. AID PROJECT
	PLOT DATE = 12/23/2010	DATE - 12/23/2010	REVISED -							