

90% FED.
10% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 0003	STRUCTURAL 0013	LANDSCAPING 0031
63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	150	150		
X6350120	DELINEATOR REMOVAL	EACH	40	40		
63700175	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT	FOOT	141	141		
63700275	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	10,225	10,225		
X6370279	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT (SPECIAL)	FOOT	141	141		
63700805	CONCRETE BARRIER TRANSITION	FOOT	174	174		
63700900	CONCRETE BARRIER BASE	FOOT	18,006	18,006		
64200105	SHOULDER RUMBLE STRIPS	FOOT	49,630	49,630		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	4	4		
66700705	FURNISHING AND ERECTING DRAINAGE MARKERS	EACH	7	7		
67100100	MOBILIZATION	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	7	7		
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	85,460	85,460		
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	1,810	1,810		

* DENOTES SPECIALTY ITEM

90% FED.
10% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 0003	STRUCTURAL 0013	LANDSCAPING 0031
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	210	210		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	29,903	29,903		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	42,080	42,080		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	3,500	3,500		
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	522	522		
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	18,410	18,410		
* 72000100	SIGN PANEL-TYPE 1	SQ FT	13	13		
* 72000200	SIGN PANEL-TYPE 2	SQ FT	466	466		
* 72000300	SIGN PANEL-TYPE 3	SQ FT	1,980	1,980		
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	10	10		
* 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	18	18		
* 72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	22	22		
* 72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	2,013	2,013		
* 72600100	MILEPOST MARKER ASSEMBLY	EACH	16	16		
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	76	76		

m:\proj\3384\3_001\design\misc\plan\3384E-50004.dgn



USER NAME = jkellman	DESIGNED - CRC	REVISED -
PLOT SCALE = 1/8" = 1' IN.	DRAWN - JMK	REVISED -
PLOT DATE = 10/28/2010	CHECKED - MRJ	REVISED -
	DATE - 10/27/2010	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**F.A.I. 80 FROM NS RAILROAD TO US 45
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	9915&5-11 Y-1	WILL	309	7
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60M59	

Rev.