

90% FED.
10% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 0003	STRUCTURAL 0013	LANDSCAPING 0031
50105220	PIPE CULVERT REMOVAL	FOOT	15	15		
X6370250	CONCRETE BARRIER, VARIABLE CROSS-SECTION 42" HEIGHT	FOOT	6,380	6,380		
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	12	12		
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1		
X8050010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	3	3		
X8130360	JUNCTION BOX, COMPOSITE CONCRETE, EMBEDDED IN STRUCTURE, 20" X 13" X 12"	EACH	2	2		
X8360105	LIGHT POLE FOUNDATION, INTEGRAL WITH BARRIER WALL, 24" DIAMETER	FOOT	70	70		
X8710035	FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	53,500	53,500		
X8710036	FIBER OPTIC CABLE 12 F SM	FOOT	3,300	3,300		
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	51,210	51,210		
Z0012710	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	61	61		
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES SQ FT)		24		24	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0014800	CULVERT TO BE CLEANED	FOOT	1,714	1,714		
Z0023600	FILLING EXISTING CULVERTS	EACH	2	2		

* DENOTES SPECIALTY ITEM
 Δ NON-PARTICIPATING

90% FED.
10% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 0003	STRUCTURAL 0013	LANDSCAPING 0031
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	1	1		
Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	7	7		
Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	10	10		
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	595	595		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		
Z0056220	SAND MODULE IMPACT ATTENUATOR TO BE REMOVED	EACH	2	2		
Z0064800	SELECTIVE CLEARING	UNIT	998			998
Z0065700	SLOPE WALL REPAIR	SQ YD	108		108	
Z0076600	TRAINEES	HOUR				
Z0076870	UNDERDRAIN CONNECTION TO STRUCTURE	EACH	88	88		
44200577	CLASS A PATCHES, TYPE II, 12 INCH	SQ YD	40	40		
44200581	CLASS A PATCHES, TYPE III, 12 INCH	SQ YD	140	140		
X2503110	MOWING (SPECIAL)	ACRE	0.25			0.25
X2503315	INTERSEEDING, CLASS 4 (MODIFIED)	ACRE	23			23

r:\pro\3384\3\asst\design\misc\3384-50027.dgn

ENGINEERING CONSULTANT
Gioba Group, Inc.
 CONSULTING ENGINEERS
 5017 North Cumberland Avenue, Suite 402
 Chicago, Illinois 60630
 Tel: 773.775.4000 Fax: 773.775.4014
 Email: Chicago@gioba.com

USER NAME = jk.jellman	DESIGNED - CRC	REVISED -
PLOT SCALE = 1/8" = 1' IN.	DRAWN - JMK	REVISED -
PLOT DATE = 10/28/2010	CHECKED - MRJ	REVISED -
	DATE - 10/27/2010	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**F.A.I. 80 FROM NS RAILROAD TO US 45
 SUMMARY OF QUANTITIES**

SCALE:	SHEET NO. OF SHEETS	STA. TO STA.
--------	---------------------	--------------

F.A.I. RTE. 80	SECTION 99(5&5-1) Y-1	COUNTY WILL	TOTAL SHEETS 309	SHEET NO. 10
CONTRACT NO. 60M59				
ILLINOIS FED. AID PROJECT				

Rev.