


STATION			STAGE 1					STAGE 2				
			20200100		20201200			20200100		20201200		
			EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
I-80 FROM NS RAILROAD TO US 45			(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
882+50.00	TO	883+00.00	37.4	31.8	28.9	8.3	23.5	0.0	0.0	0.0	0.0	0.0
883+00.00	TO	884+00.00	70.0	59.5	65.4	19.8	39.7	0.0	0.0	0.0	0.0	0.0
884+00.00	TO	885+00.00	69.1	58.7	65.2	19.3	39.5	0.0	0.0	0.0	0.0	0.0
885+00.00	TO	886+00.00	68.5	58.2	65.6	21.1	37.1	0.0	0.0	0.0	0.0	0.0
886+00.00	TO	887+00.00	62.8	53.4	62.2	30.4	23.0	0.0	0.0	0.0	0.0	0.0
887+00.00	TO	888+00.00	51.9	44.1	58.5	53.9	-9.8	0.0	0.0	0.0	0.0	0.0
888+00.00	TO	889+00.00	41.1	34.9	62.4	85.4	-50.4	0.0	0.0	0.0	0.0	0.0
889+00.00	TO	890+00.00	41.5	35.3	62.4	82.6	-47.3	0.0	0.0	0.0	0.0	0.0
890+00.00	TO	891+00.00	53.1	45.2	58.5	45.2	0.0	0.0	0.0	0.0	0.0	0.0
891+00.00	TO	892+00.00	60.2	51.2	58.5	27.8	23.4	0.0	0.0	0.0	0.0	0.0
892+00.00	TO	893+00.00	64.6	54.9	58.5	22.2	32.7	0.0	0.0	0.0	0.0	0.0
893+00.00	TO	894+00.00	75.0	63.8	58.5	9.3	54.5	0.0	0.0	0.0	0.0	0.0
894+00.00	TO	895+00.00	86.1	73.2	58.5	2.6	70.6	0.0	0.0	0.0	0.0	0.0
895+00.00	TO	896+00.00	97.6	83.0	58.5	0.2	82.8	0.0	0.0	0.0	0.0	0.0
896+00.00	TO	897+00.00	102.2	86.9	58.5	0.0	86.9	0.0	0.0	0.0	0.0	0.0
897+00.00	TO	897+72.49	43.6	37.1	34.8	13.6	23.5	0.0	0.0	0.0	0.0	0.0
899+84.45	TO	900+00.00	7.1	6.0	6.5	3.3	2.8	0.0	0.0	0.0	0.0	0.0
900+00.00	TO	901+00.00	62.0	52.7	51.5	19.4	33.3	0.0	0.0	0.0	0.0	0.0
901+00.00	TO	902+00.00	65.2	55.4	58.5	20.4	35.0	0.0	0.0	0.0	0.0	0.0
902+00.00	TO	903+00.00	69.6	59.2	58.3	17.6	41.6	0.0	0.0	0.0	0.0	0.0
903+00.00	TO	904+00.00	69.3	58.9	58.3	15.6	43.3	0.0	0.0	0.0	0.0	0.0
904+00.00	TO	905+00.00	64.4	54.8	58.5	15.4	39.4	0.0	0.0	0.0	0.0	0.0
905+00.00	TO	906+00.00	65.0	55.3	58.5	12.2	43.0	0.0	0.0	0.0	0.0	0.0
906+00.00	TO	907+00.00	66.5	56.5	58.5	14.1	42.4	0.0	0.0	0.0	0.0	0.0
907+00.00	TO	908+00.00	67.2	57.1	58.5	20.0	37.1	0.0	0.0	0.0	0.0	0.0
908+00.00	TO	909+00.00	64.4	54.8	58.5	26.1	28.7	0.0	0.0	0.0	0.0	0.0
909+00.00	TO	910+00.00	63.9	54.3	58.5	23.5	30.8	98.7	83.9	30.2	0.2	83.7
910+00.00	TO	911+00.00	66.1	56.2	58.5	18.7	37.5	244.1	207.5	68.3	0.4	207.1
911+00.00	TO	912+00.00	66.1	56.2	58.5	17.4	38.8	344.3	292.6	81.7	0.7	291.9
912+00.00	TO	913+00.00	65.7	55.9	58.5	20.4	35.5	394.6	335.4	97.0	1.1	334.3
913+00.00	TO	914+00.00	68.0	57.8	62.2	19.4	38.3	406.7	345.7	109.3	0.9	344.7
914+00.00	TO	915+00.00	69.6	59.2	62.2	13.9	45.3	419.4	356.5	116.3	0.9	355.6
915+00.00	TO	916+00.00	68.5	58.2	58.5	14.6	43.6	323.3	274.8	121.7	1.9	273.0
916+00.00	TO	917+00.00	64.1	54.5	58.5	18.9	35.6	160.9	136.8	108.3	2.0	134.8
917+00.00	TO	918+00.00	60.9	51.8	58.5	18.1	33.6	72.8	61.9	85.6	2.4	59.5
918+00.00	TO	919+00.00	64.6	54.9	58.5	13.0	42.0	26.7	22.7	48.7	6.5	16.2
919+00.00	TO	920+00.00	63.9	54.3	58.5	14.3	40.0	0.0	0.0	26.7	18.9	-18.9
920+00.00	TO	921+00.00	62.0	52.7	58.5	14.6	38.1	0.0	0.0	59.6	129.3	-129.3
921+00.00	TO	922+00.00	75.4	64.1	58.5	7.2	56.8	0.0	0.0	61.9	138.9	-138.9
922+00.00	TO	923+00.00	86.9	73.8	61.5	2.6	71.2	0.0	0.0	33.0	28.1	-28.1
923+00.00	TO	924+00.00	83.5	71.0	64.4	4.4	66.5	61.5	52.3	63.7	6.5	45.8
924+00.00	TO	925+00.00	78.9	67.1	64.4	4.6	62.4	79.6	67.7	76.7	2.2	65.5
925+00.00	TO	926+00.00	80.9	68.8	64.4	2.8	66.0	18.1	15.4	27.4	0.2	15.2
926+00.00	TO	927+00.00	86.1	73.2	61.5	2.4	70.8	0.0	0.0	0.0	0.0	0.0
927+00.00	TO	928+00.00	87.2	74.1	58.5	17.2	56.9	0.0	0.0	0.0	0.0	0.0
928+00.00	TO	929+00.00	91.1	77.4	58.5	15.7	61.7	0.0	0.0	0.0	0.0	0.0
929+00.00	TO	930+00.00	84.3	71.6	58.5	3.0	68.7	0.0	0.0	0.0	0.0	0.0
930+00.00	TO	931+00.00	82.2	69.9	58.5	3.0	66.9	0.0	0.0	0.0	0.0	0.0
931+00.00	TO	931+50.00	44.4	37.7	30.2	0.1	37.6	0.0	0.0	9.2	5.3	-5.3
931+50.00	TO	931+65.00	12.9	11.0	9.3	0.1	10.9	0.0	0.0	5.6	3.3	-3.3
931+65.00	TO	932+00.00	30.3	25.7	21.1	0.3	25.5	0.0	0.0	9.4	5.2	-5.2

N:\PROJ\328A\328A_V1_East\Design\Wpac\Sheets\328A-E-EW_schem01.dgn

 Giorba Group, Inc. CONSULTING ENGINEERS <small>2527 North Cumberland Avenue, Suite 402 Chicago, Illinois 60659 Tel: 773.775.4008 Fax: 773.775.4014 Email: ceng@giorgroup.com</small>	USER NAME = jk.jellman	DESIGNED - CRC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	F.A.I. 80 FROM NS RAILROAD TO US 45 EARTHWORK SCHEDULES	F.A.I. RTE. = 80	SECTION = 99(5&5-1) Y-1	COUNTY = WILL	TOTAL SHEETS = 309	SHEET NO. = 16
	PLOT SCALE = 1/8" = 1' / IN.	CHECKED - MRJ	REVISED -			SCALE:	SHEET NO. OF SHEETS STA. TO STA.	CONTRACT NO. 60M59 ILLINOIS FED. AID PROJECT		
PLOT DATE = 10/28/2010	DATE = 10/27/2010	REVISED -	REVISED -							