	Code No.	Item Description	UNIT	URBAN TOTAL QUANTITIES	100% STATE ROADWAY J060-2A	TRAFFIC SIGNAL Y031-IF	Y060 ELMHURST 100%	100% STATE LIGHTING Y030-IE	TRAF SURV. Y032-IF
					CONSTRUCTION TYPE CODE				
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	100	100				
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	200	200				
	20200100	EARTH EXCAVATION	CU YD	30,813	30,813				
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	510	510				
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	510	510				
	20800150	TRENCH BACKFILL	CU YD	1,204	1,204				
*	21101615	TOPSOIL, FURNISH AND PLACE, 4"	SQ YD	24,627	24,627				
*	21101630	TOPSOIL, FURNISH AND PLACE, 8"	SQ YD	36,324	36,324				
*	21101685	TOPSOIL, FURNISH AND PLACE, 24"	SQ YD	4,288	4,288				
*	25000210	SEEDING, CLASS 2A	ACRE	6.0	6.0				
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	538.0	538.0				
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	538.0	538.0				
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	538.0	538.0				
*	25001800	SEEDING, CLASS 4 (MODIFIED)	ACRE	7.5	7.5				
*	25100630	EROSION CONTROL BLANKET	SQ YD	65,238.0	65,238.0				
*	25200110	SODDING, SALT TOLERANT	SQ YD	1590	1590				
*	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	5,392.0	5,392.0				
*	25200200	SUPPLEMENTAL WATERING	UNIT	25	25				
	28000305	TEMPORARY DITCH CHECKS	FOOT	635.5	635.5				
	28000315	AGGREGATE DITCH CHECKS	TON	22.0	22.0				
	28000400	PERIMETER EROSION BARRIER	FOOT	13,713.5	13,713.5				
	28000510	INLET FILTERS	EACH	25	25				
	28001000	AGGREGATE (EROSION CONTROL)	TON	30	30				
	28100107	STONE RIPRAP, CLASS A4	SQ YD	11	11				
	28200200	FILTER FABRIC	SQ YD	11	11				
	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	107	107				
	31101600	SUB-BASE GRANULAR MATERIAL, TYPE B 8"	SQ YD	44	44				
	35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	415	415				
	35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	357	357				
	35501302	HOT-MIX ASPHALT BASE COURSE, 4 1/2"	SQ YD	707	707				
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	71	71				
	40600635	LEVELING BINDER (MACHINE METHOD), N 70	TON	106	106				
	40600962	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	133	133				

LOCATION OF WORK:
F.A.U. 3537 - U.S. 20 (LAKE STREET)
WALNUT STREET TO YORK STREET
DUPAGE COUNTY

* SPECIALITY ITEM

FILE NAME = Quant_SHT_ALL.dgn	USER NAME = Matt Rempfer IDOT V8	DESIGNED -	REVISED -
		DRAWN - DR	REVISED -
	PLOT SCALE = 50.0000 ' / in.	CHECKED - SRG	REVISED -
	PLOT DATE = 5/7/2010	DATE - 1/18/10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. | SHEET NO. 4 OF SHEETS | STA. N/A | TO STA. N/A

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3537	(4Y & 22-31R-2	DUPAGE	284	4
		CONTRACT NO. 62093		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		