

Code No.	Item Description	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
				100% STATE		100% STATE		
				ROADWAY J000-2A	TRAFFIC SIGNAL Y031-IF	Y060 ELMHURST 100%	LIGHTING Y030-IE	TRAF SURV. Y032-IF
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	33	33				
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N 90	TON	408	408				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N 90	TON	568	568				
42000506	PORTLAND CEMENT CONCRETE PAVEMENT, 10 1/4" (JOINTED)	SQ YD	24,461	24,461				
42001300	PROTECTIVE COAT	SQ YD	34,525	34,525				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	287	287				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3,012	3,012				
44000100	PAVEMENT REMOVAL	SQ YD	29,615	29,615				
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	3,983	3,983				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	341	341				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	9,839	9,839				
44000600	SIDEWALK REMOVAL	SQ FT	2,875	2,875				
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	201	201				
44003100	MEDIAN REMOVAL	SQ FT	19,817	19,817				
44004000	PAVED DITCH REMOVAL	FOOT	227	227				
44004250	PAVED SHOULDER REMOVAL	SQ YD	6,083	6,083				
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	11	11				
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	17	17				
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	147	147				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,778	1,778				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,217	1,217				
48300505	PORTLAND CEMENT CONCRETE SHOULDERS, 10 1/4"	SQ YD	5,717	5,717				
50105220	PIPE CULVERT REMOVAL	FOOT	108	108				
50300225	CONCRETE STRUCTURES	CU YD	35	35				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,632	1,632				
54001038	BOX CULVERT END SECTION, CULVERT NO. 38	EACH	1	1				
54010502	PRECAST CONCRETE BOX CULVERT 5' X 2'	FOOT	109	109				
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	5	5				
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1				
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	5	5				
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	987	987				

LOCATION OF WORK:
F.A.U. 3537 - U.S. 20 (LAKE STREET)
WALNUT STREET TO YORK STREET
DUPAGE COUNTY

* SPECIALITY ITEM

FILE NAME =
Quant_SHT_ALL.dgn

USER NAME = Matt Remper IDOT VB	DESIGNED -	REVISED -
PLOT SCALE = 50,000' / in.	DRAWN - DR	REVISED -
PLOT DATE = 4/23/2010	CHECKED - SRG	REVISED -
	DATE - 1/18/10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 4 OF SHEETS STA. N/A TO STA. N/A

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3537	4Y & 22-3R-2	DUPAGE	284	5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 62093	